

SIGNING SCHEDULE								
LOCATION	OFFSET	TYPE	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	DECORATIVE SIGN POST (EA)	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	COMMENTS
IL RTE 159								
169+67	27' RT	R8-3	4.0				12	
169+69	27' LT	R8-3	4.0				12	
170+83	27' RT	R2-1	7.5				13	
171+47	27' RT	R8-3	4.0				12	
172+10	27' RT	W3-3	9.0				14	
173+43	31' RT	R8-3	4.0				12	
173+44	31' LT	R8-3	4.0				14	
175+50	33' LT	R8-3	4.0				14	
176+18	33' LT	R2-1	7.5				15	
178+52	33' RT	R2-1	7.5		13			
180+11	33' RT	R3-9B		12.0	14			
180+29	33' LT	R8-3	4.0		12			
180+31	33' RT	R8-3	4.0		12			
182+00	33' RT	R8-3	4.0		12			
182+08	33' LT	W3-3	9.0		14			
183+04	33' LT	R8-3	4.0		12			
184+26	38' LT	R3-9B		12.0	14			
184+92	33' LT	R8-3	4.0		12			
185+10	39' RT	R5-1	9.0		15			
185+30	33' LT	R2-1	7.5		13			
185+43	39' RT	R5-1	9.0		15			
188+49	33' RT	R2-1	7.5		13			
189+27	42' RT	R1-1	9.0		15			
189+40	33' LT	M3-1	4.5		15			
		MI-1100	9.0					
189+49	33' RT	R3-9B		12.0	14			
189+73	33' LT	R8-3	4.0		12			
191+33	33' LT	R3-9B		12.0	14			
192+10	33' RT	STREET	1.5		10			AUTUMN AVE VANDALIA ST
		STREET	1.5					
192+21	33' RT	M3-1	4.5		15			
		MI-1100	9.0					
192+99	33' LT	R8-3	4.0		12			
193+81	33' RT	R8-3	4.0		12			
193+83	33' LT	R8-3	4.0		12			
195+47	33' RT	R8-3	4.0		12			
196+62	33' LT	R8-3	4.0		12			
197+33	33' RT	R8-3	4.0		12			
199+12	33' RT	R3-9B		12.0	14			
200+13	33' LT	R3-9B		12.0	14			
202+26	33' RT	R8-3	4.0		12			
202+42	33' RT	R2-1	7.5		13			
202+72	33' LT	R8-3	4.0		12			
203+40	33' RT	R3-1	6.3		13			
		R3-2	6.3					
203+50	38' RT	R5-1	9.0		15			
203+90	38' RT	R5-1	9.0		15			
204+53	33' RT	R8-3	4.0		12			
205+06	33' LT	R8-3	4.0		12			
207+79	43' RT	R1-1	9.0		15			
207+81	42' RT	STREET	1.8		15			HIGH SCHOOL ST VANDALIA ST
		STREET	1.5					
208+09	33' RT	R2-1	7.5		13			
209+02	33' LT	R3-9B		12.0	14			
209+28	33' RT	R3-9B		12.0	14			
210+51	33' LT	R8-3	4.0		14			MOUNT EX. ADOPT A STREET SIGN WITH R8-3
211+02	33' RT	R8-3	4.0		12			
216+83	33' RT	MI-1100	9.0		15			
		M3-1	4.5					
217+21	33' LT	R3-9B		12.0	14			
217+64	33' LT	MI-1100	9.0		15			
		M3-1	4.5					
219+14	33' RT	R3-9B		12.0	14			
219+57	33' RT	R8-3	4.0		12			
220+33	33' RT	R2-1	7.5		13			
226+28	33' LT	R3-9B		12.0	14			
226+68	33' LT	R8-3	4.0		14			
227+87	33' RT	R8-3	4.0		12			
229+19	33' RT	R3-9B		12.0	16			
230+08	33' LT	R8-3	4.0		14			
230+59	33' LT	R2-1	7.5		15			
233+89	38' LT	STREET	1.5		12			MOUNDS AVE VANDALIA ST
		STREET	1.5					
234+01	50' LT	R1-1	9.0		15			
236+07	33' LT	R3-9B		12.0	16			
236+88	48' RT	R1-1	9.0		15			
236+98	35' RT	STREET	2.0		12			CUMBERLAND AVE VANDALIA ST
		STREET	1.5					
SUBTOTAL 1			349	156	805	0	118	

SIGNING SCHEDULE								
LOCATION	OFFSET	TYPE	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	DECORATIVE SIGN POST (EA)	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	COMMENTS
E JOHNSON ST								
11+43	22' RT	R1-1	9.0			1		
		R3-2	6.3					
		STREET SIGN	1.5					E JOHNSON ST VANDALIA ST
		STREET SIGN	1.5					
11+55	1' RT	R1-1	9.0			1		
		R3-2	6.3					
11+70	1' RT	R5-1	9.0				13	
12+28	2' LT	R5-1	9.0				13	
12+37	0' RT	R1-1	9.0			1		
		R3-2	6.3					
12+53	21' LT	R1-1	9.0			1		
		R3-2	6.3					
		STREET SIGN	1.5					E JOHNSON ST VANDALIA ST
		STREET SIGN	1.5					
ALLEY 168+75								
0+27	17' LT	R3-2	6.3				13	
0+36	13' LT	R1-1	9.0			1		
E MADISON AVE								
0+28	0' RT	R5-1	9.0				13	
0+43	1' LT	R1-1	9.0			1		
		R3-2	6.3					
0+55	22' LT	R1-1	9.0			1		
		R3-2	6.3					
		STREET SIGN	1.5					MADISON AVE VANDALIA ST
		STREET SIGN	1.5					
E WICKLIFFE AVE								
60+66	23' LT	R10-11B	4.0		12			
60+84	28' RT	R8-3	4.0		12			
KEEBLER								
		W14-1	4.0		15			LOCATE AT THE INTERSECTION WITH E WASHINGTON ST
VALLEY AVE								
0+46	31' LT	STREET SIGN	1.5		15			VALLEY AVE VANDALIA ST
		STREET SIGN	1.5					
0+46	29' LT	R1-1	9.0		15			
VALLEY LN								
0+68	19' LT	STREET SIGN	1.5		15			VALLEY LN VANDALIA ST
		STREET SIGN	1.5					
0+67	18' LT	R1-1	9.0		15			
E PARK AVE								
60+01	15' RT	R8-3	4.0		14			
69+03	39' LT	R2-1	5.0		17			
		R8-3	4.0					
69+09	17' RT	R8-3	4.0		14			
SPRING ST								
81+73	18' LT	R8-3	4.0		12			
81+32	18' RT				15			REMOVE EXISTING SIGNS AND MOUNT ON NEW SUPPORTS
ALLEY 190+65								
0+43	12' LT	R1-1	9.0		15			
AUTUMN AVE								
90+58	35' LT	R1-1	9.0		13			
91+90	17' LT	W3-1A	9.0		16			
BROWN AVE								
0+45	38' LT	STREET SIGN	1.5		15			BROWN AVE VANDALIA ST
		STREET SIGN	1.5					
0+45	36' LT	R1-1	9.0		15			
ALLEY 193+03								
0+71	20' LT	R1-1	9.0		15			
ALLEY 194+20								
0+43	13' LT	R1-1	9.0		15			
WADSWORTH ST								
0+42	22' LT	STREET SIGN	1.8		13			WADSWORTH ST VANDALIA ST
		STREET SIGN	1.5					
0+42	20' LT	R1-1	9.0		13			
SUBTOTAL 2			269	0	301	7	52	

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
P:\Projects\513501\CADD\DN\0876885-sht\schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 48.0000' / in.		CHECKED -	REVISED -
PLOT DATE = 3/5/2013		DATE - 01/25/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: N/A      SHEET NO. 10 OF 31 SHEETS      STA. N/A      TO STA. N/A

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-3	MADISON	529	44
<b>CONTRACT NO. 76B85</b>				
ILLINOIS FED. AID PROJECT				