

STRIPING SCHEDULE (CONT'D)

LOCATION	TYPE	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID						RAISED REFLECTIVE PAVEMENT MARKERS		PAINT PAVEMENT MARKING CURB	PRISMATIC CURB REFLECTOR	
		LETTERS & SYM (SQ FT)	4" STRIPE		8" STRIPE	12" STRIPE		24" STRIPE	ONE WAY (EA)			TWO WAY (EA)
			WHITE (FT)	YELLOW (FT)	WHITE (FT)	WHITE (FT)	YELLOW (FT)	WHITE (FT)				
ILLINOISAVE	CROSSWALK						152					
	STOP BAR							24				
	DIAGONAL						32					
	SOLID				45							
MEADOW LN	CROSSWALK						127					
	STOP BAR							24				
	DIAGONAL						23					
	SOLID				40							
CALIFORNIAAVE	CROSSWALK						142					
	STOP BAR							24				
	DIAGONAL						26					
	SOLID				39							
CLAREMONT CT	CROSSWALK						119					
	STOP BAR							22				
MOUNDS AVE	CROSSWALK						83					
	STOP BAR							15				
CUMBERLAND AVE	CROSSWALK						110					
	STOP BAR							21				
SUBTOTAL (3)		0	0	0	124	814	0	130	0	0	0	
SUBTOTAL (1)		1195	4661	21018	121	1536	126	380	211	333	450	
SUBTOTAL (2)		0	0	308	39	1966	0	264	0	4	0	
SUBTOTAL (3)		0	0	0	124	814	0	130	0	0	0	
TOTAL		1195	25987		284	4442		774	548	450	55	

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
P:\Projects\513501\CADD\DN\0876885-sht	schedule.dgn	DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/25/2013	DATE - 01/25/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: N/A SHEET NO. 13 OF 31 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-3	MADISON	529	47
CONTRACT NO. 76B85			ILLINOIS FED. AID PROJECT	