

PIPE SCHEDULE (CONT'D)

UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	STORM SEWERS, CLASS A, TYPE 1 (FT)	STORM SEWERS, CLASS A, TYPE 2 (FT)								PIPE DRAINS, 6" (FT)	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 (FT)	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 (FT)						STORM SEWERS, TYPE 2 WATER MAIN QUALITY PIPE (FT)				TRENCH BACKFILL (CY)
			12"	12"	15"	18"	24"	30"	36"	42"			48"	12"	12"	15"	18"	24"	36"	42"	12"	15"	
VALLEY																							
INLET 5-60	INLET 5-57																	31				10	
WEST PARK																							
INLET 5-43	INLET 5-46		23																			5	
INLET 5-46	MH 5-42		106																			27	
INLET 5-42	MH 5-42		24																			7	
MH 5-42	INLET 5-45		87																			30	
INLET 5-45	MH 5-41			42																		27	
INLET 5-41	MH 5-41		35																			11	
MH 5-41	MH 5-45			94																		75	
INLET 5-44	MH 5-45		15																			10	
MH 5-45	MH 5-44				41																	44	
ALLEY 190+65																							
INLET 6-2	INLET 6-3		22																			6	
INLET 6-3A	INLET 6-3		41																			12	
BROWN																							
INLET 6-6	INLET 6-7										46											12	
ALLEY 194+20																							
INLET 6-10	INLET 6-11		20																			8	
WADSWORTH																							
INLET 6-13	INLET 6-14										38											10	
REBECCA																							
INLET 6-19	INLET 6-18										33											8	
ALLEY 199+96																							
INLET 6-33	INLET 6-34																	18				5	
TILLOTSON																							
INLET 6-35	MH 6-21																		78			22	
INLET 6-36	INLET 6-35										28											6	
ALLEY 201+69																							
INLET 6-22	INLET 6-21			18																		7	
MARY																							
INLET 6-39	INLET 6-38										51											12	
HIGH SCHOOL																							
INLET 7-5	INLET 7-6										53											13	
UNION																							
INLET 7-27	INLET 7-26																	47				12	
INDIANA																							
INLET 8-18	MH 8-17																					9	
INLET 8-19	INLET 8-18			26																		6	
INLET 8-24	INLET 8-19		36																			8	
INLET 8-20	INLET 8-19			43																		10	
INLET 8-23	INLET 8-20		28																			6	
INLET 8-21	INLET 8-20			59																		13	
INLET 8-22	INLET 8-21		29																			6	
EX INLET	INLET 8-21	11																				1	
ALLEY 223+94																							
INLET 8-25	MH 8-25		13																			7	
INLET 8-26	MH 8-25			11																		7	
ILLINOIS																							
INLET 8-30	INLET 8-28		49																			13	
INLET 8-29	INLET 8-28			87																		31	
CALIFORNIA																							
INLET 9-14	MH -14																			25		5	
INLET 9-15	INLET 9-14										29											6	
INLET 9-16	INLET 9-15		7																			1	
CLAREMONT																							
INLET 9-20	INLET 9-21		7																			1	
INLET 9-21	INLET 9-22			43																		10	
SUBTOTAL (4)		11	542	379	85	0	0	0	0	0	0	249	29	32	0	0	0	96	78	0	25	517	
SUBTOTAL (1)		82	1128	242	281	0	539	395	82	285	40	189	52	120	163	0	0	275	0	0	0	2125	
SUBTOTAL (2)		91	828	360	442	342	74	594	0	0	0	124	262	0	150	241	0	551	57	10	0	1467	
SUBTOTAL (3)		0	558	261	338	294	0	464	375	0	0	231	0	98	54	0	50	544	112	85	0	1205	
SUBTOTAL (4)		11	542	379	85	0	0	0	0	0	0	249	29	32	0	0	0	96	78	0	25	517	
TOTALS		184	3056	1242	1146	636	613	1453	457	285	40	40	793	343	250	367	241	50	1466	247	95	25	5314

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
P:\Projects\513501\CADD\DN\0876885-sht\schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE - 01/25/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: N/A SHEET NO. 18 OF 31 SHEETS STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-3	MADISON	529	52
CONTRACT NO. 76B85				
ILLINOIS FED. AID PROJECT				