STRUCTURE SCHEDULE (CONT'D)

STATION	OFFSET	STRUCTURE	SURFACE (ELEV)	INVERT (ELEV)	DEPTH (FT)	MANHOLE, TYPE A (EA)								PRECAST REINFORECED CONCRETE FLAT SLAB TOP (EA) ••TO BE INCLUDED IN COST OF MANHOLE	CLASS SI CONCRETE (OUTLET) STD 606211 (CU YD)	GRATES & COVERS, TYPE 2B STD 606211 (EA)	CATCHBASINS TYPE C, TYPE 8 GRATE (EA)	INLETS, TYPE A, TYPE 3 FRAME & GRATE (EA)	INLETS, TYPE B, TYPE 3 FRAME & GRATE (EA)	INLETS, SPECIAL, TYPE E (EA)		
						4'-DIAMETER TY 1 FRAME, CLOSED LID	4'-DIAMETER TY 3 FRAME & GRATE	5'-DIAMETER TY 1 FRAME, OPEN LID	5'-DIAMETER TY 1 FRAME, CLOSED LID	5'-DIAMETER TY 3 FRAME & GRATE	6'-DIAMETER TY 1 FRAME, CLOSED LID	6'-DIAMETER TY 3 F&G, TY 1 FR, CLOSED LID, RESTRICTOR PLATE	6'-DIAMETER, WITH 2 TY 1 FRAME, CLOSED LID, RESTRICTOR PLATE							4'x4'	4'x5'	4'x6'
ALLEY 223+94																						
0+45.74	4.02' LT	MH 8-25	543.65	537.29	6.36	1								1								
0+48.53	9.00' RT	INLET 8-25	543.54	538.04	5.50													1				
0+54.10	10.90' LT	INLET 8-26	543.66	537.65	6.01														1			
ILLINOIS																						
0+51.42	16.00' RT	INLET 8-28	546.39	539.09	7.30		1															
0+73.15	27.74' LT	INLET 8-30	546.28	540.28	6.00													1				
1+38.36	21.03' RT	INLET 8-29	548.00	543.00	5.00													1				
CALIFORNIA																						
0+75.06	18.17' RT	MH 9-14	546.50	542.20	4.30			1						1								
0+94.33	14.22' LT	INLET 9-16	546.51	542.51	4.00													1				
1+01.16	16.11' RT	INLET 9-14	546.93	542.33	4.60																1	
1+01.16	13.53' LT	INILET 9-15	546.43	542.47	3.96														1			
CLAREMONT																						
0+42.94	25.16' RT	INLET 9-20	548.74	544.70	4.04													1				
0+48.67	21.15' RT	INLET 9-21	548.59	544.65	3.94														1			
0+48.67	21.66' LT	INLET 9-22	548.65	544.40	4.25														1			
SUBTOTAL (5)						1	1	1	0	0	0	0	0	2	0	0	0	5	4	0	1	0
SUBTOTAL (1)						8	1	0	7	4	9	1	2	25	4	2	5	25	16	0	0	0
SUBTOTAL (2)						7	1	0	13	10	0	0	2	21	0	0	0	22	19	0	0	0
SUBTOTAL (3)						6	4	0	6	6	0	1	1	17	0	0	1	19	19	4	5	1
SUBTOTAL (4)						3	0	0	0	0	0	0	0	3	0	0	1	16	21	0	0	0
SUBTOTAL (5)						1	1	1	0	0	0	0	0	2	0	0	0	5	4	0	1	0
TOTALS						25	7	1	26	20	9	2	5	68	4	2	7	87	79	4	6	1