

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021		
CODE NO	ITEM	UNIT					CODE NO	ITEM	UNIT				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4	4			
67100100	MOBILIZATION	L SUM	1	1		81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	25	25			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	40676	40676			
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		X0325077	FIBER OPTIC UTILITY MARKER	EACH	54	54			
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1		X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	46378	46378			
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1		X0327597	WARNING PLATE	EACH	3	3			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
80300100	LOCATING UNDERGROUND CABLE	FOOT	40500	40500		*25000210	SEEDING, CLASS 2A	ACRE	4.6	4.6			
81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	250	250		*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	418	418			
81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2" DIA.	FOOT	40500	40500		*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	418	418			
81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	450	450		*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	418	418			
						*25100105	MULCH, METHOD 1	ACRE	4.6	4.6			
						28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	418	418			

*SPECIALTY ITEM

**FAI 270/FAI 255/FAI 55/70

FILE NAME *	USER NAME = prstonne	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE:	SHEET OF SHEETS STA. TO STA.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwr\work\puidot\prstonne\d0219800\d0219800\76f77\sh-t-lts.dgn		DRAWN -	REVISED -						DIST 8 ITS 2013-1	MADISON	28	3
		CHECKED -	REVISED -									
		DATE -	REVISED -									

CONTRACT NO. 76F77
ILLINOIS FED. AID PROJECT