

PAVEMENT MARKING SCHEDULE

LOCATION			TEMPORARY PAVEMENT MARKING						THERMOPLASTIC PAVEMENT MARKING						PAVEMENT MARKING REMOVAL SQ FT	SHORT-TERM PAVE MARKING WHITE (2 LIFTS) FOOT	SHORT-TERM PAVE MARKING YELLOW (2 LIFTS) FOOT	WORKZONE PAVE MARKING REMOVAL SQ FT	
			4" - SOLID (WHITE) FOOT	4" - SOLID (YELLOW) FOOT	4" - SKIP DASH (WHITE) FOOT	8" - SOLID (WHITE) FOOT	8" - SKIP DASH (WHITE) FOOT	12" - SOLID (WHITE) FOOT	4" - SOLID (WHITE) FOOT	4" - SOLID (YELLOW) FOOT	4" - SKIP DASH (WHITE) FOOT	8" - SOLID (WHITE) FOOT	8" - SKIP DASH (WHITE) FOOT	12" - SOLID (WHITE) FOOT					
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
I-270 EASTBOUND																			
258+00	TO	295+59	3759	3759	940				3759	3759	940				2819	984	301	214	
295+59	TO	318+11	2252	2252	563	850	128	588	2252	2252	563	850	128	588	2929	590	180	128	
324+03	TO	334+51	1048	1048	262				1048	1048	262				786	274	84	60	
337+33	TO	382+50	4517	4517	1235				4517	4517	1235				3423	1259	361	270	
382+50	TO	400+22	1772	1772	443	564	162		1772	1772	443	564	162		1813	464	142	101	
402+46	TO	438+88	3642	3642	1818	1192	986		3642	3642	1818	1192	986		4486	1016	291	218	
438+88	TO	489+37	5049	5049	2525	50			5049	5049	2525	50			4241	2838	404	540	
489+37	TO	515+81	2644	2644	1862	524			2644	2644	1862	524			2733	1566	212	296	
516+19	TO	533+84	1765	1765	1010				1765	1765	1010				1513	876	141	169	
533+84	TO	557+23	2339	2339	1923	718	432		2339	2339	1923	718	432		2967	1528	187	286	
557+23	TO	607+50	5027	5027	2059	214			5027	5027	2059	214			4180	1957	402	393	
607+50	TO	645+51	3801	3801	950				3801	3801	950				2851	995	304	217	
648+21	TO	685+89	3768	3768	942				3768	3768	942				2826	987	301	215	
689+72	TO	726+57	3685	3685	921	850	70		3685	3685	921	850	70		3377	965	295	210	
726+57	TO	795+08	6851	6851	1794	248			6851	6851	1794	248			5331	1853	548	400	
797+65	TO	858+35	6070	6070	1518	1024	101		6070	6070	1518	1024	101		5302	1589	486	346	
860+68	TO	871+97	1129	1129	282	322	49		1129	1129	282	322	49		1094	296	90	64	
874+62	TO	880+04	542	542	136				542	542	136				407	142	43	31	
I-270 WESTBOUND																			
258+10	TO	296+35	3825	3825	956				3825	3825	956				2869	1001	306	218	
296+35	TO	318+27	2192	2192	720	1020			2192	2192	720	1020			2381	697	175	145	
324+19	TO	334+33	1014	1014	254				1014	1014	254				761	265	81	58	
337+19	TO	382+72	4553	4553	1138	682	116	307	4553	4553	1138	682	116	307	4253	1192	364	259	
382+72	TO	400+44	1772	1772	595	410	53		1772	1772	595	410	53		1688	575	142	119	
402+68	TO	443+47	4079	4079	2133	1378	678		4079	4079	2133	1378	678		4801	1878	326	367	
443+47	TO	515+81	7234	7234	3617	1246	147		7234	7234	3617	1246	147		6957	3209	579	631	
516+19	TO	560+37	4418	4418	3148	170			4418	4418	3148	170			4108	2643	353	499	
560+37	TO	590+00	2963	2963	1407	490	97		2963	2963	1407	490	97		2835	1260	237	249	
590+00	TO	645+21	5521	5521	1380				5521	5521	1380				4141	1445	442	315	
647+91	TO	686+17	3826	3826	957				3826	3826	957				2870	1002	306	218	
690+00	TO	732+75	4275	4275	1153	1456	67		4275	4275	1153	1456	67		4250	1180	342	254	
732+75	TO	794+50	6175	6175	1544				6175	6175	1544				4631	1617	494	352	
797+07	TO	858+75	6168	6168	1647	570			6168	6168	1647	570			5041	1691	493	364	
861+00	TO	885+66	2466	2466	665	916	62		2466	2466	665	916	62		2518	681	197	146	
IL 157 RAMP 1																			
146+97	TO	153+93	696	646	135	360			696	646	135	360			732	154	56	35	
IL 157 RAMP 2																			
257+22	TO	274+33	1711	1661	553	50			1711	1661	553	50			1342	539	137	113	
IL 157 RAMP 3																			
6+21	TO	13+95	774	774		50			774	774		50			549	62	62	21	
IL 157 RAMP 4																			
1+33	TO	10+20	887	887		50			887	887		50			625	71	71	24	
IL 159 RAMP 1																			
2+37	TO	10+18	781	731		50			781	731		50			537	62	62	21	
IL 159 RAMP 2																			
5+56	TO	14+18	862	812		50			862	812		50			591	69	69	23	
IL 159 RAMP 3																			
14+61	TO	17+26	265	265		50			265	265		50			210	21	21	7	
IL 159 RAMP 4																			
2+37	TO	9+73	736	736		50			736	736		50			524	59	59	20	
SUBTOTAL			126853	126653	43182	15604	3146	895	126853	126653	43182	15604	3146	895	112291	41552	10148	8617	
TOTAL			296688			18750			895	296688			18750			895	51700		8617