

SUMMARY OF QUANTITIES

FAP 329(IL 154)	
80%FED/20% STATE	
RURAL	URBAN
RESURFACING	
PERRY COUNTY	
CONSTRUCTION TYPE CODE 0005	CONSTRUCTION TYPE CODE 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
* X7801000	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING-LETTERS & SYMBOLS	SO FT	122.4	0	122.4
* X7801004	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	168,369	146,367	22,002
* X7801006	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	71	0	71
* X7801024	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	153	29	124
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	20.3	20.3	0.0
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	11.3	11.3	0.0
Z0034105	MATERIAL TRANSFER DEVICE	TON	15,180	13,310	1,870
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	1
Z0100209	STONE RIPRAP, CLASS A5	TON	65	65	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	32,514	28,450	4,064
40600300	AGGREGATE (PRIME COAT)	TON	538	471	67
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	7,588	6,648	940
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	735	514	221
40600990	TEMPORARY RAMP	SQ YD	45	15	30
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	15,180	13,310	1,870
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	799	566	233
44000152	HOT-MIX ASPHALT SURFACE REMOVAL - 3/4"	SQ YD	165,886	152,783	13,103
44000158	HOT-MIX ASPHALT SURFACE REMOVAL - 2 1/4"	SQ YD	12,624	3,574	9,050
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SQ YD	69	58	11
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	3,814	3,349	465
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	437	437	0
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	614	614	0
48100500	AGGREGATE SHOULDERS, TYPE A 6 INCH	SQ YD	858	858	0
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	1,093	1,006	87
58100200	WATERPROOF MEMBRANE SYSTEM	SQ YD	929	929	0

*SPECIALTY ITEM

FILE NAME :	USER NAME : *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwwork\pwwork\mccordr\100332891\78351-sh\plan.dgn		DRAWN -	REVISED -			329	(19,18,17,103)RS-4	PERRY	34	5	
#MODELNAME#	PLOT SCALE : 200.0000 1/ in.	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 78351			
	PLOT DATE : 3/22/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					