

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	Existing Length (Inform. Only)	GUARDRAIL REMOVAL	SPBGR. TYPE A. 6 FT. POSTS	TRAFFIC BARRIER TERMINAL, TY. 1 SPL. (TANG)	SPBGR ATTACHED TO STRUCTURE	L. S. GUARDRAIL OVER CULV., 25' SPAN	TERMINAL MARKERS - DA	GUARDRAIL MARKERS TY. A	STRUCTURE REPAIR OF CONC. (+ 5")	STRUCTURE REPAIR OF CONC. (+5")	STONE RIPRAP, CLASS A5
	FOOT	FOOT	FOOT	EACH	FOOT	FOOT	EACH	EACH	S. F.	S. F.	TONS
FAP 329 (IL 154)											
073-7046 (North Side)											
LT 488+32.50				1			1				
LT 488+54.00 TO LT 489+44.00	90	90									
LT 488+82.50 TO LT 489+20.00					37.5			4			
LT 489+70.00				1			1				
073-7048 (North Side)											
LT 530+21.50				1			1				
LT 530+42.00 TO LT 531+32.00	90	90									
LT 530+71.50 TO LT 531+09.00					37.5			4			
LT 531+59.00				1			1				
073-7048 (South Side)											
RT 530+21.00				1			1				
RT 530+64.00 TO RT 531+28.00	64	64									
RT 530+50.00 TO RT 530+71.00								2			
RT 530+71.00 TO RT 531+08.50					37.5			2	1.5		
RT 531+58.50				1			1				
073-7050 (North Side)											
LT 577+65.00											65
073-7051 (North Side)											
LT 624+70.00				1			1				
LT 624+94.00 TO LT 625+69.00	75	75									
LT 625+20.00 TO LT 625+45.00					25			2	18.8		
LT 625+45.00 TO LT 625+70.00			25					2			
LT 626+20.00				1			1				
073-7051 (South Side)											
RT 623+95.00				1			1				
RT 625+09.00 TO RT 625+79.00	70	70									
RT 624+45.00 TO RT 626+20.00						175		4	11.3		
RT 626+70.00				1			1				
073-7055 (North Side) (Stationing decreasing)											
LT 139+35.50				1			1				
LT 139+16.00 TO LT 138+26.00	90	90									
LT 138+85.50 TO LT 138+48.00					37.5			4			
LT 137+98.00				1			1				
073-7055 (South Side)											
RT 138+98.00				1			1				
RT 139+20.00 TO RT 138+30.00	90	90									
RT 138+48.00 TO RT 138+10.50					37.5			4			
RT 137+60.50				1			1				
073-7056 (North Side)											
LT 61+43.00				1			1				
LT 61+45.00 TO LT 60+55.00	90	90									
LT 60+93.00 TO LT 59+93.00			100					4			
LT 59+43.00				1			1				
073-7056 (South Side)											
RT 61+94.00				1			1				
RT 61+45.00 TO RT 60+55.00	90	90									
RT 61+44.00 TO RT 60+56.50			87.5					4			
RT 60+06.50				1			1				
073-7057 (North Side)											
LT 1332+07.00				1			1				
LT 1331+75.00 TO LT 1330+98.00	77	77									
LT 1331+57.00 TO LT 1330+57.00			100					4			
LT 1330+07.00				1			1				
PROJECT TOTALS:		826	312.5	20	212.5	175	20	40	20.3	11.3	65

Note 1: Any widening necessary to construct the Type 1, Special (Tangent) Guardrail Terminal shall be included in the cost of the TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT).

FILE NAME :	USER NAME : \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\mccordkr\d0332891\78351-sht-plan.dgn		DRAWN -	REVISED -			329	(19,18,17,103)RS-4	PERRY	34	12	
\$MODELNAME\$		CHECKED -	REVISED -			CONTRACT NO. 78351					
	PLOT SCALE : 200.0000' / in.	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO