

04-102373V.ppt 2006/02/20 2:01:29 PM

### SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FEDERAL, 10% STATE								
				DAN RYAN J000-2A	DAN RYAN I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNING Y002-1C	STRUCTURAL			
									Y007 WALL C	X771-2A SNO16-2852	SFTY-2A SNO16-0073	
31102300	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SQ YD	828.0								828	
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	754		754							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.1	0.2	8.9							
40600300	AGGREGATE (PRIMECOAT)	TON	46	1	45							
40600895	CONSTRUCTING TEST STRIP	EACH	2		2							
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	56		56							
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2757	2757								
42001300	PROTECTIVE COAT	SQ YD	195021	191537	3484							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	391								391	
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	127554	127554								
42101426	LUG SYSTEM COMPLETE 26'	EACH	3	3								
42101436	LUG SYSTEM COMPLETE 36'	EACH	1	1								
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	17684	17684								
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3107	147	2960							
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	6733		6733							
44000100	PAVEMENT REMOVAL	SQ YD	117763	117763								
44000106	BITUMINOUS REMOVAL OVER PATCHES 1 1/2"	SQ YD	669		669							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	17884	15337	2547							
44001980	CONCRETE BARRIER REMOVAL	FOOT	13112	12192	920							
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	4918	4918								
44004250	PAVED SHOULDER REMOVAL	SQ YD	42464	39986	2478							
44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	2044	2044								
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	4372	4372								
44201427	CLASS C PATCHES, TYPE II, 16 INCH	SQ YD	134		134							
44201431	CLASS C PATCHES, TYPE III, 16 INCH	SQ YD	148		148							
44201433	CLASS C PATCHES, TYPE IV, 16 INCH	SQ YD	422		422							
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	11,709	11,709								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	379	379								
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	1237		1237							
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1								1	
50102400	CONCRETE REMOVAL	CU YD	19	2				12	5			
50200100	STRUCTURE EXCAVATION	CU YD	5910	616					821	4473		
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	242								242	

- \* - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- - NON-PARTICIPATING

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**F.A.I. 94 (DAN RYAN EXPRESSWAY)**

**SUMMARY OF QUANTITIES**  
**SHEET 2 OF 9**

SCALE: NONE      DRAWN BY: RTM  
DATE: MARCH 7, 2006      CHECKED BY: MPG

Rev-