



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2016

SUBJECT: FAI Route 80 (I-80)
Section 99-4-1-SB-B-R
Will County
Contract No. 60V71
Item No. 13, June 10, 2016 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page 33 of the Special Provisions
3. Revised sheets 1,2 & 6 of the Plans
4. Added sheets 46A-46N to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; D. Carl Puzey; Estimates

MS/ck

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -

Code - 197 - -

District - 1 - -

Section Number - 99-4-1-SB-B-R

Project Number

*REVISED: MAY 27, 2016

Route

FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2002920	T-CELTIS OCCID 2-1/2	EACH	4.000				
A2007116	T-QUERCUS RUBRA 2	EACH	5.000				
B0001720	T-AMEL X GF AP SF 12'	EACH	9.000				
C2002048	S-CORYLUS AMER 4'	EACH	20.000				
D2001984	E-PICEA GLAU DEN 7'	EACH	8.000				
K0029634	WEED CONTR PRE-EM GRN	POUND	38.000				
X0322508	PED TRUSS SUPERSTR	SQ FT	3,372.000				
X5860110	GRANULAR BACKFILL STR	CU YD	30.000				
X6431120	REM IMP ATTEN SM	EACH	2.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				
X7040125	PIN TEMP CONC BARRIER	EACH	532.000				
X7240600	REM RE-ERECT EX SIGN	EACH	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0022800	FENCE REMOVAL	FOOT	472.000				
Z0030850	TEMP INFO SIGNING	SQ FT	52.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-4-1-SB-B-R

Project Number
 *REVISED: MAY 27, 2016

Route
 FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0046304	P UNDR FOR STRUCT 4	FOOT	83.000				
Z0064800	SELECTIVE CLEARING	UNIT	2.500				
Z0076604	TRAINEES TPG	HOUR	1,000.000		15.000		15,000.000
20100110	TREE REMOV 6-15	UNIT	507.000				
20100210	TREE REMOV OVER 15	UNIT	108.000				
20101100	TREE TRUNK PROTECTION	EACH	55.000				
20101300	TREE PRUN 1-10	EACH	25.000				
20101350	TREE PRUN OVER 10	EACH	25.000				
20200100	EARTH EXCAVATION	CU YD	371.000				
20200200	ROCK EXCAVATION	CU YD	1,399.000				
20400800	FURNISHED EXCAVATION	CU YD	506.000				
20800150	TRENCH BACKFILL	CU YD	69.000				
21101505	TOPSOIL EXC & PLAC	CU YD	456.000				
21101615	TOPSOIL F & P 4	SQ YD	92.000				
25000115	SEEDING CL 1B	ACRE	0.250				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -

Code - 197 - -

District - 1 - -

Section Number - 99-4-1-SB-B-R

Project Number

*REVISED: MAY 27, 2016

Route

FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000210	SEEDING CL 2A	ACRE	1.000				
25000310	SEEDING CL 4	ACRE	1.000				
25000400	NITROGEN FERT NUTR	POUND	205.000				
25000600	POTASSIUM FERT NUTR	POUND	205.000				
25100105	MULCH METHOD 1	ACRE	0.750				
25100115	MULCH METHOD 2	ACRE	0.250				
25100630	EROSION CONTR BLANKET	SQ YD	13,309.000				
28000250	TEMP EROS CONTR SEED	POUND	183.000				
28000305	TEMP DITCH CHECKS	FOOT	160.000				
28000400	PERIMETER EROS BAR	FOOT	1,020.000				
28000510	INLET FILTERS	EACH	8.000				
28100107	STONE RIPRAP CL A4	SQ YD	76.000				
28200200	FILTER FABRIC	SQ YD	76.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	45.000				
31101400	SUB GRAN MAT B 6	SQ YD	625.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -

Code - 197 - -

District - 1 - -

Section Number - 99-4-1-SB-B-R

Project Number

*REVISED: MAY 27, 2016

Route

FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40201000	AGGREGATE-TEMP ACCESS	TON	1,774.000				
40603340	HMA SC "D" N70	TON	69.000				
44000100	PAVEMENT REM	SQ YD	710.000				
44004250	PAVED SHLD REMOVAL	SQ YD	45.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	20.000				
48203013	HMA SHOULDERS 4	SQ YD	45.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50102400	CONC REM	CU YD	26.100				
50157300	PROTECTIVE SHIELD	SQ YD	414.000				
50200100	STRUCTURE EXCAVATION	CU YD	82.000				
50200400	ROCK EXC STRUCT	CU YD	20.000				
*ADD 50300225	CONC STRUCT	CU YD	112.400				
*DEL 50300255	CONC SUP-STR	CU YD	11.100				
50300300	PROTECTIVE COAT	SQ YD	50.000				
*REEV 50301350	CONC SUPSTR APP SLAB	CU YD	11.100				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-4-1-SB-B-R

Project Number
 *REVISED: MAY 27, 2016

Route
 FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800105	REINFORCEMENT BARS	POUND	890.000				
50800205	REINF BARS, EPOXY CTD	POUND	19,810.000				
51500100	NAME PLATES	EACH	2.000				
51603000	DRILLED SHAFT IN SOIL	CU YD	4.100				
51604000	DRILLED SHAFT IN ROCK	CU YD	4.800				
5421D024	P CUL CL D 1 24 TEMP	FOOT	200.000				
54210192	PIPE ELBOW 36	EACH	2.000				
54213459	END SECTIONS 24	EACH	4.000				
550B0160	STORM SEW CL B 1 36	FOOT	110.000				
58700300	CONCRETE SEALER	SQ FT	1,181.000				
59100100	GECOMPOSITE WALL DR	SQ YD	19.000				
60224445	MAN TA 7 DIA T1F OL	EACH	2.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	437.500				
63100167	TR BAR TRM T1 SPL TAN	EACH	1.000				
63200310	GUARDRAIL REMOV	FOOT	470.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60V71

State Job # - C-91-061-13

County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 99-4-1-SB-B-R

Project Number
 *REVISED: MAY 27, 2016

Route
 FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63301210	REM RE-E SPBGR TY A	FOOT	100.000				
64300450	IMP ATTN NRD TL3	EACH	2.000				
64301090	ATTENUATOR BASE	SQ YD	33.000				
66400305	CH LK FENCE 6	FOOT	336.000				
67000400	ENGR FIELD OFFICE A	CAL MO	12.000				
67100100	MOBILIZATION	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	12.000				
70400100	TEMP CONC BARRIER	FOOT	2,100.000				
70600260	IMP ATTN TEMP FRN TL3	EACH	4.000				
78000200	THPL PVT MK LINE 4	FOOT	1,780.000				
78000500	THPL PVT MK LINE 8	FOOT	730.000				
78200410	GUARDRAIL MKR TYPE A	EACH	6.000				
78200530	BAR WALL MKR TYPE C	EACH	168.000				
78201000	TERMINAL MARKER - DA	EACH	1.000				
78300100	PAVT MARKING REMOVAL	SQ FT	830.000				

CONTRACT NUMBER

60V71

THIS IS THE TOTAL BID

\$ _____

NOTES:

1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.
2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.
3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.
4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS: 701101, 701400, 701401, 701411, 701428, 701446, 701901,
704001

DETAILS: TC-08, TC-09, TC-12, TC-17, TC-18

SPECIAL PROVISIONS: MAINTENANCE OF ROADWAYS
PUBLIC CONVENIENCE AND SAFETY (DIST 1)
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC
TRAFFIC CONTROL FOR WORK ZONE AREAS
TEMPORARY INFORMATION SIGNING
SPEED DISPLAY TRAILER (D1)

Revised 6/1/16