SUMMARY OF QUANTITIES				100% STATE
				6-00995-0000
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005 URBAN
67100100	MOBILIZATION	L SUM	1	1
⚠ * 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,906	1,906
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FT	26,994	26,994
⚠ ~~* 78007100~~	~~PERMANENT PAVEMENT MARKING - LETTERS AND SYMBOLS~~	~~SQ FT~~	~~1,906~~	~~1,906~~
X0325800	PARKING LOT SEAL COAT	SQ YD	35,915	35,915
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1

* SPECIALTY ITEM

⚠ REVISED 6-2-16

FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 6\Projects\0672J19\Contracts\GADsheets\0672J19-sht-500.dgn	USER NAME = Veronskifo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED -			VAR	*	SANGAMON	10	3
Default	PLOT SCALE = 100.0000 ' / in.	DATE -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 72J19		
	PLOT DATE = 5/2/2016		REVISED -				ILLINOIS	FED. AID PROJECT		

ADMIN BLDG PARKING LOT-2016

PARKING LOT SEAL COAT	
LOCATION	SEAL COAT (SQ YD)
BAY 1	1726
BAY 2	1731
BAY 3	1734
BAY 4	1731
BAY 5	1734
BAY 6	1731
BAY 7	1734
BAY 8	1731
BAY 9	1731
BAY 10	1734
BAY 11	1731
BAY 12	1734
BAY 13	1731
BAY 14	1734
BAY 15	1731
BAY 16	1734
BAY 17	255
BAY 18	556
RING ROAD	7392
	35,915

*QUANTITIES MEASURED IN CAD

PAVEMENT MARKING	
LOCATION	PAINT PAVEMENT MARKING - LINE 4" (FT)
	YELLOW
BAY 1	1232
BAY 2	1227
BAY 3	1229
BAY 4	1229
BAY 5	1232
BAY 6	1229
BAY 7	1224
BAY 8	1564
BAY 9	1569
BAY 10	1232
BAY 11	1227
BAY 12	1230
BAY 13	1239
BAY 14	1232
BAY 15	1227
BAY 16	1345
BAY 17	596
BAY 18	788
RING ROAD	5143
TOTAL	26,994

*QUANTITIES MEASURED IN CAD

1

PAINT PAVEMENT MARKING - LETTERS & SYMBOLS		
TYPE LOCATION	QUANTITY	(SQ FT)
		WHITE
LEFT ARROW	18	280.8
BAYS 1 -16		
RIGHT ARROW	1	15.6
RING ROAD		
THROUGH & LEFT ARROW	19	494
RING ROAD		
THROUGH & RIGHT ARROW	1	26
RING ROAD		
HANDICAP	26	80.6
BAYS 8-9, BAYS 16-18, RING ROAD		
NUMBERED PARKING SPACES	97 SPACES	993.6
BAYS 15-16 , NUMBERS 1 -97		
YIELD SYMBOL	5	15
RING ROAD		
TOTAL		1,906

*QUANTITIES CALCULATED USING "LARGE SIZE" WHERE APPLICABLE

1 REVISED 6-2-16

FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 6\Projects\D672J19-sht-schedule	USER NAME = Veronskifo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -			VAR	*	SANGAMON	10	4
Default	PLOT DATE = 5/2/2016	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			CONTRACT NO. 72J19		
		DATE -	REVISED -					ILLINOIS FED. AID PROJECT		

ADMIN BLDG PARKING LOT-2016