

ROADWAY
 90% FED.
 10% STATE
 URBAN

RETAINING WALLS

BOX CULVERTS

SIGNING

ELECTRICAL

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				J000-2A	Y007	Y007	Y002-1C	Y030-1E
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	17,155	17,155				
40600300	AGGREGATE (PRIME COAT)	TON	23	23				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	568	568				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,575	1,575				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	79	79				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	152	152				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,099	1,099				
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	15,892	15,892				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	29,074	29,074				
42001300	PROTECTIVE COAT	SQ YD	41,638	41,638				
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SQ YD	1,384	1,384				
44000100	PAVEMENT REMOVAL	SQ YD	40,795	40,795				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,349	1,349				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	6,660	6,660				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,270	3,270				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,875	2,875				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	724	724				
44004250	PAVED SHOULDER REMOVAL	SQ YD	405	405				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	299	299				
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	6,754	6,754				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	7,936	7,936				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5,193	5,193				
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	876	876				
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	11,037	11,037				
50200100	STRUCTURE EXCAVATION	CU YD	1,364	1,364				
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2,581.1	144.1	2,437.0			
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	950	702	248			
50300225	CONCRETE STRUCTURES	CU YD	400	400				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	54,484	54,104	380			
50900200	STEEL RAILING, TYPE 2399	FOOT	20		20			
54010503	PRECAST CONCRETE BOX CULVERT 5'X3'	FOOT	455		455			
54010603	PRECAST CONCRETE BOX CULVERT 6'X3'	FOOT	840		840			
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	282	282				

* SPECIALTY ITEM

FILE NAME =	USER NAME = TKluergel
D:\60C31-SHT-50002.dgn	
PLOT SCALE = 1:50	
PLOT DATE = 12/16/2009	

DESIGNED - MJT	REVISED -
DRAWN - MJT	REVISED -
CHECKED - DLT	REVISED -
DATE - 12/18/09	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 7 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(99-1&2)AC-3	WILL	524	6
CONTRACT NO. 60C31				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.

FINAL