

EARTHWORK SCHEDULE RAMP C

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL / UNSUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE	ROCK EXCAVATION
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
2003+50.00	2004+50.00	439	110	375	100	275	0	65
2004+50.00	2005+50.00	363	120	310	100	210	0	35
2005+50.00	2006+50.00	371	145	315	95	220	0	0
2006+50.00	2007+50.00	489	185	415	80	335	0	0
2007+50.00	2008+50.00	730	200	620	40	580	0	0
2008+50.00	2009+50.00	993	220	845	0	845	0	0
2009+50.00	2010+50.00	1,160	265	985	0	985	0	0
2010+50.00	2011+50.00	1,147	300	975	0	975	0	0
2011+50.00	2012+50.00	845	325	720	0	720	0	0
2012+50.00	2013+50.00	675	360	575	0	575	0	5
2013+50.00	2014+50.00	793	410	675	0	675	0	10
2014+50.00	2015+50.00	913	480	775	0	775	0	5
2015+50.00	2016+50.00	517	530	440	395	45	0	0
2016+50.00	2017+14.00	169	360	145	300	-155	0	100
2017+14.00	2017+50.00	202	210	170	150	20	0	65
2017+50.00	2018+00.00	316	295	270	380	-110	0	25
2018+00.00	2018+50.00	308	275	260	450	-190	0	15
2018+50.00	2019+50.00	365	445	310	1,350	-1,040	0	15
2019+50.00	2020+50.00	445	450	380	1,890	-1,510	0	5
2020+50.00	2021+50.00	569	535	485	2,260	-1,775	0	0
2021+50.00	2022+50.00	458	535	390	2,900	-2,510	0	0
2022+50.00	2023+50.00	521	510	445	3,585	-3,140	0	0
2023+50.00	2024+50.00	386	490	330	4,200	-3,870	0	0
2024+50.00	2025+50.00	347	495	295	4,885	-4,590	0	10
2025+50.00	2026+50.00	708	510	600	5,625	-5,025	0	140
2026+50.00	2027+25.00	495	460	420	6,510	-6,090	0	100
2027+25.00	2027+50.00	144	180	120	2,790	-2,670	0	30
2027+50.00	2028+50.00	886	650	755	12,040	-11,285	0	145
2028+50.00	2029+50.00	462	285	395	6,555	-6,160	0	30
2029+50.00	2030+50.00	0	0	0	0	0	0	0
2030+50.00	2031+50.00	0	305	0	6,460	-6,460	0	0
2031+50.00	2032+25.00	0	475	0	9,320	-9,320	0	0
2032+25.00	2032+50.00	271	170	230	3,300	-3,070	0	180
2032+50.00	2033+50.00	1,084	635	920	12,615	-11,695	0	715
2033+50.00	2034+50.00	0	510	0	9,315	-9,315	0	0
2034+50.00	2035+50.00	0	390	0	6,735	-6,735	0	0
2035+50.00	2036+50.00	0	335	0	5,250	-5,250	0	0
2036+50.00	2037+50.00	0	305	0	4,315	-4,315	0	0
SUB TOTAL		17,571	13,460	14,945	113,990	-99,045	0	1,695

EARTHWORK SCHEDULE RAMP D

BEGIN STATION	END STATION	EARTH EXCAVATION	TOPSOIL / UNSUITABLE EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE*	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR EMBANKMENT, SUBGRADE	ROCK EXCAVATION
		CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
4001+00.00	4002+00.00	526	235	445	635	-190	0	45
4002+00.00	4003+00.00	636	310	540	615	-75	0	65
4003+00.00	4004+00.00	549	305	465	555	-90	0	65
4004+00.00	4005+00.00	560	250	475	410	65	0	110
4005+00.00	4006+00.00	613	215	520	285	235	0	120
4006+00.00	4007+00.00	334	145	285	180	105	0	70
4007+00.00	4008+00.00	139	85	120	175	-55	0	30
4008+00.00	4009+00.00	132	65	110	150	-40	0	25
SUB TOTAL		3,489	1,610	2,960	3,005	-45	0	530

\* ASSUME 15% FOR SHRINKAGE

FILE NAME = D:\62031-SHT-SCHEDULE06.dgn	USER NAME = TKluegel	DESIGNED - TRK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.I. RTE. 55	SECTION (99-1&2)AC-3	COUNTY WILL	TOTAL SHEETS 524	SHEET NO. 23
PLOT SCALE = 1:500	CHECKED - DLT	REVISED -	SCALE: NONE					SHEET NO. 6 OF 11 SHEETS	STA.	TO STA.	CONTRACT NO. 60C31	
PLOT DATE = 12/14/2009	DATE - 12/18/09	REVISED -	FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT									