

SUMMARY OF QUANTITIES

URBAN
100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X031-2A STRUCTURE	I000-2A ROADWAY
50102400	CONCRETE REMOVAL	CU YD	79	79	0
50157300	PROTECTIVE SHIELD	SQ YD	331	331	0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	79	79	0
50300530	FLOOR DRAIN EXTENSION	EACH	21	21	0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4730	4730	0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9090	9090	0
50800515	BAR SPLICERS	EACH	104	104	0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	464	464	0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24	24	0
52100510	ANCHOR BOLTS, 3/4"	EACH	2	2	0
52100520	ANCHOR BOLTS, 1"	EACH	48	48	0
58700300	CONCRETE SEALER	SQ FT	38245	38245	0
59000200	EPOXY CRACK INJECTION	FOOT	154	154	0
59200101	BRIDGE WASHING NO. 1	EACH	1	1	0
59200102	BRIDGE WASHING NO. 2	EACH	1	1	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	0	5
67100100	MOBILIZATION	L SUM	1	0	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	0	4
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4019	0	4019
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1100.0	0	1100.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1100.0	0	1100.0
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	37	0	37
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6987	0	6987
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	614	0	614
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	840	0	840
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	307	0	307
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	105	0	105
* 78100300	REPLACEMENT REFLECTOR	EACH	98	0	98
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	356	0	356
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3750	0	3750

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X031-2A STRUCTURE	I000-2A ROADWAY
X0320532	CONCRETE BRIDGE DECK SCARIFICATION (3/8" INCH)	SQ YD	2575	2575	0
X0320887	POLYMER CONCRETE	CU FT	10.0	10.0	0
X0321468	PLUG EXISTING DECK DRAINS	EACH	23	23	0
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	200	0	200
X0322944	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	2575	2575	0
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	317	317	0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	409	409	0
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4"	FOOT	11607	0	11607
X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6"	FOOT	177	0	177
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24"	FOOT	94	0	94
X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8"	FOOT	72	0	72
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	30	0	30
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	0.7	0.7	0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	21.1	21.1	0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	14.5	14.5	0
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	0	2
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	0	2
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	2	2	0
X0326909	CENTER LOCK ADJUSTMENT	EACH	2	2	0

*Specialty Items

FILE NAME =	USER NAME = #USER#	DESIGNED - SEW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL-43 (HARLEM AVE.) OVER SANITARY AND SHIP CANAL	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - SEW	REVISED -			348	(0708.1 & 2323.5)B	COOK	47	03	
		CHECKED - FML	REVISED -			CONTRACT NO. 60D69					
		DATE - 03/2010	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.			

Rev.