

SUMMARY OF QUANTITIES			URBAN 100% STATE		100% STATE		SUMMARY OF QUANTITIES			URBAN 100% STATE		100% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X081-2A	CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X081-2A		
20101100	TREE TRUNK PROTECTION	EACH	3	3		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	76	76			
20200100	EARTH EXCAVATION	CU YD	157	157		44000700	APPROACH SLAB REMOVAL	SQ YD	249		249		
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	232	232		44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	553	553			
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1		44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	220	220			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9		44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	3624	3624			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9		44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	73	73			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	88	88			
25100630	EROSION CONTROL BLANKET	SQ YD	232	232		44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	59	59			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1		
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60		50102400	CONCRETE REMOVAL	CU YD	12.0		12.0		
28000400	PERIMETER EROSION BARRIER	FOOT	544	544		50300225	CONCRETE STRUCTURES	CU YD	37.4		37.4		
28000510	INLET FILTERS	EACH	6	6		50300255	CONCRETE SUPERSTRUCTURE	CU YD	188.3		188.3		
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	76	76		50300260	BRIDGE DECK GROOVING	SQ YD	184		184		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		50300300	PROTECTIVE COAT	SQ YD	688		688		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	52	52		50400205	PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH)	SQ FT	1650		1650		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	37	37		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	50390		50390		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	183	183		50800515	BAR SPLICERS	EACH	247		247		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9	9		50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	97		97		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	122	122		51500100	NAME PLATES	EACH	1		1		
42001430	BRIDGE APPROACH CONNECTOR (FLEXIBLE)	SQ YD	86	86		59000200	EPOXY CRACK INJECTION	FOOT	6		6		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	56	56		60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	2	2		
44000100	PAVEMENT REMOVAL	SQ YD	183	183									
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1116	1116									

\* SPECIALTY ITEMS



DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, SLV	REVISED -
DATE - 03/26/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 59 OVER FLINT CREEK TRIBUTARY**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 98+00 TO STA. 101+60

F.A.P. RTE. 338	SECTION 108 B-1	COUNTY LAKE	TOTAL SHEETS 40	SHEET NO. 3
D-91-289-09			CONTRACT NO. 60F92	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.