

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A ROADWAY
20200100	EARTH EXCAVATION	CU YD	1	1
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,537	4,537
20400800	FURNISHED EXCAVATION	CU YD	1,848	1,848
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,165	1,165
20800150	TRENCH BACKFILL	CU YD	65	65
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,481	3,481
25000210	SEEDING, CLASS 2A	ACRE	0.72	0.72
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65	65
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65	65
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65	65
25100630	EROSION CONTROL BLANKET	SQ YD	3,481	3,481
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	72	72
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60
28000400	PERIMETER EROSION BARRIER	FOOT	1,145	1,145
28100107	STONE RIPRAP, CLASS A4	SQ YD	27	27
28200200	FILTER FABRIC	SQ YD	27	27
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2,845	2,845
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	2,845	2,845
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	168	168
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	252	252
44000100	PAVEMENT REMOVAL	SQ YD	762	762
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	157	157
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,369	1,369
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	67	67
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	116	116
50105220	PIPE CULVERT REMOVAL	FOOT	62	62

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A ROADWAY
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	225	225
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	89	89
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	2	2
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1
60107600	PIPE UNDERDRAINS 4"	FOOT	100	100
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	12	12
67000400	ENGINEERS FIELD OFFICE TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
* 72000100	SIGN PANEL - TYPE 1	SQ FT	36	36
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	11	11
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	80	80
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,658	1,658
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	508	508
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14
* 78100300	REPLACEMENT REFLECTOR	EACH	34	34
78300100	PAVEMENT MARKING REMOVAL	SQ FT	110	110
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	714	714
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102	102
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

* DENOTES SPECIALTY ITEM

N:\Jobs\2009\20090322\931\road\plan\100\100168046-11-500.dgn

FILE NAME =	USER NAME = _USER_	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 53 AT MIDWIN NATIONAL TALLGRASS PRAIRIE SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 50.0045' / IN.	DRAWN - EF	REVISED -			846	5N	WILL	26	3	
	PLOT DATE = 3/26/2010	CHECKED - RS	REVISED -			CONTRACT NO. 60G46					
		DATE - 03/26/2010	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE: NTS	SHEET NO. 1 OF 1 SHEETS		STA.	TO STA.		