



LEGEND:

- DECK SLAB REPAIR (PARTIAL)
- CONCRETE REMOVAL AND CONCRETE SUPERSTRUCTURE (2 FT. EACH SIDE & JOINT FULL DEPTH)
- CONCRETE REMOVAL AND CONCRETE SUPERSTRUCTURE (10" x 6" EACH SIDE OF JOINT) PIERS 15, 21 AND 29
- STRUCTURAL REPAIR OF CONCRETE > 5"

* LIMITS OF PROTECTIVE SHIELD

BILL OF MATERIALS

ITEM	UNIT	QUANTITY
DECK SLAB REPAIR (PARTIAL)	Sq.Yd.	23
PROTECTIVE SHIELD	Sq.Yd.	1020
STRUCTURAL REPAIR OF CONCRETE >5"	Sq.Ft.	5.3

FILE NAME =	USER NAME = ttrtkosmv	DESIGNED -	REVISED -
cr:\pkl\work\PM1001\TINIAKOSMV\10101671\09-0171.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 4/15/2010		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US 122045 (LAGRANGE ROAD) NB
OVER DES PLAINES RIVER, SANTA FE DR. & RR (S.N. 016-2467)
BRIDGE DECK PATCHING PLAN**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	2009-133 I	COOK	114	114
CONTRACT NO. 60H89				
ILLINOIS FED. AID PROJECT				