SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE 1000 (80% FED. 20% STATE)	VILLAGE OF MATTESON Y031-1F (80% FED. 10% STATE 10% CITY)				
20200100	EARTH EXCAVATION	CU YD	13	13					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	19	19					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	313	313					
21400100	GRADING AND SHAPING DITCHES	FOOT	600	600					
25000312	SEEDING, CLASS 4A	ACRE	0.06	0.06					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4					
25100630	EROSION CONTROL BLANKET	SQ YD	313	313					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1292	1292					
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	592	592					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14					
40600300	AGGREGATE (PRIME COAT)	TON	67	67					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	26	26					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	380	380					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	136	136					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	41	41					
40603395	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1730	1730					
42001300	PROTECTIVE COAT	SQ YD	725	725					
44000100	PAVEMENT REMOVAL	SQ YD	50	50					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	8356	8356					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8384	8384					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1820	1820					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	7284	7284					
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	282	282					
44004250	PAVED SHOULDER REMOVAL	SQ YD	246	246					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	190	190					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	63	63					
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	188	188					
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1750	1750					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE 1000 (80% FED. 20% STATE)	VILLAGE OF MATTESON Y031-1F (80% FED. 10% STATE 10% CITY)				
	60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	3720	3720					
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	486	486					
	63200310	GUARDRAIL REMOVAL	FOOT	492	492					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
	67100100	MOBILIZATION	L SUM	1	1					
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2320	2320					
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11000	11000					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1000	1000					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	550	550					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	180	180					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	260	260					
*	72000100	SIGN PANEL - TYPE 1	SQ FT	20	20					
*	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	33	33					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11000	11000					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	180	180					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100					
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	597	597					
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	136	136					
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40	40					

*Specialty Items

FILE NAME = c:\pw_work\PWIDOT\SHIRANISB\d0107234\PII3907-Design.dgn	USER NAME = shiranisb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/16/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	23-N-3	COOK	38	3

CONTRACT NO. 60149

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT