

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	PARKING LANES 50% STATE 50% CITY CHICAGO 1025					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 1000	PARKING LANES 50% STATE 50% CITY CHICAGO 1025				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	31	9					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9100	9100					
40600300	AGGREGATE (PRIME COAT)	TON	190	147	43					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5400	5400					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	70	54	16					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	100	100					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1930	1480	450					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	880	880					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6700	6700					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	530	530					*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	610	610					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	295	295					*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9100	9100					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4590	3527.5	1062.5				*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5400	5400					
42001300	PROTECTIVE COAT	SQ YD	452	452					*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1550	1550					*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	880	880					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	46730	35888	10842				X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8						
44000600	SIDEWALK REMOVAL	SQ FT	1550	1550					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10						
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1260	1260					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1						
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1315	1315					88600600	DETECTOR LOOP REPLACEMENT	FOOT	232	232						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	550	550															
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	350	350															
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	200	200															
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	25	25															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	120	120															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	25	25															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	35	35															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1															
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5000	5000															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	610	610															

*Specialty Items

Rev. 5-26-10