

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN -				100% STATE	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	STRUCTURAL	
								SN016-1251 X271-2A	SN016-1252 X271-2A
* 81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	31527		3242		28285		
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	2		2				
* XQ326971	LIGHT POLE FOUNDATION (ROADWAY) MEDIAN, TYPE 1	EACH	1		1				
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	7		7				
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	22	10	12				
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	12		12				
* 87200400	SPAN WIRE	FOOT	30198				30198		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1697				1697		
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	6				6		
* 87900200	DRILL EXISTING HANDHOLE	EACH	9				9		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	17				17		
66410002	CHAIN LINK GATES, 10' X 8' DOUBLE	EACH	2	2					
42101112	LUG SYSTEM COMPLETE 12'	EACH	2	2					
* X8107510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT, SPECIAL	FOOT	99				99		
* X0326965	ELECTRIC CABLE, NO. 19 25 PAIR	FOOT	23303				23303		
X0326966	REMOVAL OF EXISTING STRUCTURES, LUG SYSTEM	SQ YD	689	689					
JT637023	CONCRETE MEDIAN BARRIER TRANSITION, TYPE V-F	FOOT	137	137					
JT213002	CONCRETE GUTTER, TYPE G3	FOOT	166	166					
JT637027	CONCRETE BARRIER, SINGLE FACE, TYPE F, MODIFIED	FOOT	210	210					
X5030225	CONCRETE STRUCTURES (SPECIAL)	CU YD	2594.2	2594.2					
X0326967	REINFORCED CONCRETE DUCT BANK REMOVAL	FOOT	9851				9851		
X5813004	ELECTRICAL CABLE IN CONDUIT, (SILV, XLP-TYPE), 3 1/2 NO. 2	FOOT	590	590					
* 81702110	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE) ^{FUSE} 1/C NO. 10	FOOT	2360		2360				
* JS813003	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 20" X 12" X 8"	EACH	2		2				
* X0326968	JUNCTION BOX, POLE OR POST MOUNTED	EACH	6				6		
* JS813007	UNIT DUCT, ^{600V} 4-1C NO. 2, 1/C NO. 2 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	284		284				
JJ213003	PAVEMENT MARKING TAPE (BLACK) 6"	FOOT	30545	30545					
JJ213004	PAVEMENT MARKING TAPE (BLACK) 8"	FOOT	22909	22909					
X0321750	REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	940	940					
* X0301576	COAXIAL CABLE IN CONDUIT	FOOT	1899				1899		
X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	4	4					
X0320801	DRAINAGE STRUCTURES, TYPE 1 (SPECIAL)	EACH	1	1					
X0320870	BRACED EXCAVATION	CU YD	1196				1196		
* X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1				1		

*SPECIALTY ITEMS

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	SHEET NO. 10
	PLOT SCALE =	DRAWN - CAC	REVISED -		SCALE: NTS	SHEET NO. 7 OF 9 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 60J27		
	PLOT DATE =	CHECKED - JDF	REVISED -		DATE - 3/18/2010							