

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN -				100% STATE	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	STRUCTURAL SNO16-1251 X271-2A	STRUCTURAL SNO16-1252 X271-2A
X7013020	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	GAL BA	399	399					
X7040010	TEMPORARY CONCRETE BARRIER (SPECIAL)	FOOT	3790	3790					
* X8160370	UNIT DUCT, WITH 3-1/2 NO. 4 AND 1/2 NO.6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	3242		3242				
* X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8'	EACH	11		11				
* X8710027	FIBER OPTIC CABLE 4 FIBERS, SINGLE MODE	FOOT	681				681		
* X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	41443				41,443		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	14415					4860	9555
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	53,113	53,113					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5				0.3	0.2
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	10	10					
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	9	9					
Z0018800	DRAINAGE SYSTEM	L SUM	1					0.80	0.20
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	6	6					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14	14					
Z0076600	TRAINEES	HOOR	0						

48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	1064	1064					
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	20,567	20,567					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2					
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4					
60224448	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
X0301892	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	28,325	28,325					
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	2	2					
550A5500	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 42"	FOOT	916	916					
X0322441	DIGITAL LOOP DETECTOR SENSOR UNIT (4 CHANNEL)	EACH	1				1		
X0322442	TONE EQUIPMENT - 3 FREQUENCY RECEIVER PROGRAMMABLE	EACH	4				4		
X0322443	TONE EQUIPMENT - 3 FREQUENCY TRANSMITTER PROGRAMMABLE	EACH	4				4		
51201800	FURNISHING STEEL PILES HP 14 X 73	FOOT	11,501	11,501					
51203800	TEST PILE HP 14 X 73	EACH	2	2					

* Specialty Items

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	Rev. SHEET NO. 11A
	PLOT SCALE =	DRAWN - CAC	REVISED -		SCALE: NTS	SHEET NO. 9 OF 9 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 60J27		
	PLOT DATE =	CHECKED - JDF	REVISED -									
	DATE - 3/18/2010	REVISED -										