SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE BRIDGE SN 045-0061 100% STATE SFTY-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	175	175
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	34	34
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	29.4	29.4
42001300	PROTECTIVE COAT	SQ YD	705	705
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	350	350
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	478	478
~~44004400~~	~~PAVEMENT REMOVAL (SPECIAL)~~	~~SQ YD~~	~~66.7~~	~~66.7~~
44201794	CLASS D PATCH, TYPE III, 12 INCH	SQ YD	40	40
44000700	APPROACH SLAB REMOVAL	SQ YD	66.7	66.7
50102400	CONCRETE REMOVAL	CU YD	18.2	18.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	38.8	38.8
50300260	BRIDGE DECK GROOVING	SQ YD	478	478
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9450	9450
52000110	PREFORMED JOINT STRIP SEAL	FOOT	98	98
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	60	60
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	478	478
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	85	85
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	14	14
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THAN OR EQUAL TO 5 INCHES)	SQ FT	165	165
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	17	17
~~X0325864~~	~~BRIDGE APPROACH PAVEMENT REMOVAL~~	~~SQ YD~~	~~66.7~~	~~66.7~~
Z0006204	BRIDGE DECK HYRDO-SCARIFICATION 1/2"	SQ YD	478	478
Z0016002	DECK SLAB REPAIR (FULL-DEPTH, TYPE II)	SQ YD	6	6
~~Z0016000~~	~~DECK SLAB REPAIR (FULL)~~	~~SQ YD~~	~~6.0~~	~~6.0~~
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1.0	1.0
~~Z0018000~~	~~DRILL AND GROUT DOWEL BARS~~	~~EACH~~	~~21~~	~~21~~

*SPECIALTY ITEMS

FILE NAME = G:\ENG\06-5329-02 DI Various Structure\CAD\0450061\Sht\DIXXXXX-sht-SOQ.dgn

Wight

USER NAME = $USER$	DESIGNED - ___	REVISED - ___ _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN - ___	REVISED - ___ _____	
PLOT SCALE = $SCALE$	CHECKED - ___	REVISED - ___ _____	
PLOT DATE = 4/1/2010	DATE - _____	REVISED - ___ _____	

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. __ OF ___ SHEETS | STA. | TO STA.

Rev.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	39-EXT-VB-1	KANE	27	3

CONTRACT NO. 60J48

ILLINOIS FED. AID PROJECT