

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE TYPE	
				BRIDGE SN 045-0034	
				100% STATE	
				SFTY-2A	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	152	152	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	529	529	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 70	TON	149	149	
50102400	CONCRETE REMOVAL	CU YD	31.9	31.9	
50157300	PROTECTIVE SHIELD	SQ YD	819	819	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	34.4	34.4	
50300260	BRIDGE DECK GROOVING	SQ YD	1331	1331	
50300300	PROTECTIVE COAT	SQ YD	1419	1419	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8580	8580	
50800515	BAR SPLICERS	EACH	26	26	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	140	140	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2304	2304	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14,450	14,450	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5585	5585	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	787	787	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	787	787	
▲ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255	255	
▲ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,600	11,600	
▲ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1050	1050	
▲ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	725	725	
▲ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3200	3200	
▲ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132	132	
▲ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	48	48	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8594	8594	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	48	48	
* X0301424	SILICONE JOINT SEALER	FOOT	23	23	
* X0320887	POLYMER CONCRETE	CU FT	1.0	1.0	

- ▲ SPECIALTY ITEMS
- SPECIAL PROVISION
- .. GUIDE BRIDGE SPECIAL PROVISION
- ... BDE SPECIAL PROVISION

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE TYPE	
				BRIDGE SN 045-0034	
				100% STATE	
				SFTY-2A	
* X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1373	1373	
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	13	13	
* X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	25	25	
* X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	5	5	
* Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	1373	1373	
* Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1	1	
* * Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* * * Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	



9901 S. Western Ave.
Chicago, IL 60643
Ph. 773-881-4788
F: 773.239.3728

DESIGNED - TBS
CHECKED - RJL
DRAWN - SCS
CHECKED - TBS

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHERIDAN RD. OVER BUCKLEY RD.
STRUCTURE NO. 049-0161

SUMMARY
OF QUANTITIES

F.A.P. RTE. 437	SECTION 71HB-1-1	COUNTY LAKE	TOTAL SHEETS 25	SHEET NO. 3
SCALE: SHEET NO. 3 OF 12 SHEETS STA. TO STA.			CONTRACT NO. 60J81	
[ILLINOIS] FED. AID PROJECT				