

ROUTE: I-80 at Houbolt Rd. - CRC Pavement Section				PATCHING = CLASS A			
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
50' East of East Approach Slab		WB	1	12	6	72	8
		WB	2	12	6	72	8
50' West of West Approach Slab		WB	1	12	6	72	8
		WB	2	12	6	72	8
TOTALS:					24		32
					FT		SY

NOTE:

PATCHES ON I-80 AT HOUBOLT RD. MAY BE LOCATED WITHIN THE LIMITS OF EXISTING LUG SYSTEM. THE CONTRACTOR SHALL TAKE EXTRA PRECAUTION WHEN REMOVING THE PATCHES, INCLUDING REMOVAL BY HAND METHODS IF NECESSARY, TO ENSURE NO DAMAGE IS CAUSED TO THE EXISTING LUG SYSTEM AND LUG REINFORCEMENT.

FILE NAME =	USER NAME = wilgreendp	DESIGNED -	REVISED - 4/28/10 - DW	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE I-80 AT HOUBOLT RD.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pki_work\PWIDOT\MILGREENDP\0183633\Design.dgn	DRAWN -	REVISED -	VAR.			2010-016PP	WILL	19	8	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60K35							
PLOT DATE = 4/28/2010	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		