

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000							CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
42101300	PROTECTIVE COAT	SO YD	4467	4467																
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150																
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	2023	2023																
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	584	584																
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	1827	1827																
44213100	PAVEMENT FABRIC	SO YD	2411	2411																
44213200	SAW CUTS	FOOT	21,432	21,432																
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																
67100100	MOBILIZATION	L SUM	1	1																
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14																
*78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	100	100																
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4170	4170																
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	820	820																
*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	100	100																
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	100	100																
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420	420																
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	400	400																
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	360	360																
Z0017202	DOWEL BARS 1 1/2"	EACH	6780	6780																
Z0075310	TIE BARS 3/4"	EACH	705	705																
* SPECIALTY ITEM																				

Rev.

FILE NAME =	USER NAME = wlgreendp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>						<b>SUMMARY OF QUANTITIES</b>						F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\paw\paw\wlgreendp\0183533\Designdgn		DRAWN -	REVISED -													VAR.	2010-019PP	COOK	18	3
		CHECKED -	REVISED -													SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
		DATE -	REVISED -									CONTRACT NO. 60K38								