

| SUMMARY OF QUANTITIES | | | URBAN 100% STATE | | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | CONSTRUCTION TYPE CODE | | | | | | |
|-----------------------|---|-----------------|---------------------|---------------|------------------------|--|--|--|--|-----------------------|------|------|------------------------|--|--|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | LAKE CD. | | | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | | | | | | |
| | | | | 1000 | | | | | | | | | | | | | | | |
| 42101300 | PROTECTIVE COAT | SO YD | 1583 | 1583 | | | | | | | | | | | | | | | |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 50 | 50 | | | | | | | | | | | | | | | |
| 44200541 | CLASS A PATCHES, TYPE II, 9 INCH | SO YD | 56 | 56 | | | | | | | | | | | | | | | |
| 44200545 | CLASS A PATCHES, TYPE III, 9 INCH | SO YD | 92 | 92 | | | | | | | | | | | | | | | |
| 44200956 | CLASS B PATCHES, TYPE II, 9 INCH | SO YD | 614 | 614 | | | | | | | | | | | | | | | |
| 44200962 | CLASS B PATCHES, TYPE III, 9 INCH | SO YD | 304 | 304 | | | | | | | | | | | | | | | |
| 44200964 | CLASS B PATCHES, TYPE IV, 9 INCH | SO YD | 505 | 505 | | | | | | | | | | | | | | | |
| 44213000 | PATCHING REINFORCEMENT | SO YD | 148 | 148 | | | | | | | | | | | | | | | |
| 44213100 | PAVEMENT FABRIC | SO YD | 809 | 809 | | | | | | | | | | | | | | | |
| 44213200 | SAW CUTS | FOOT | 4352 | 4352 | | | | | | | | | | | | | | | |
| 60262700 | INLETS TO BE RECONSTRUCTED | EACH | 1 | 1 | | | | | | | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | | | | | | | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| 70102550 | TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR | EACH | 6 | 6 | | | | | | | | | | | | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 1 | 1 | | | | | | | | | | | | | | | |
| * 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 1840 | 1840 | | | | | | | | | | | | | | | |
| * 78008220 | POLYUREA PAVEMENT MARKING TYPE I - LINE 5" | FOOT | 25 | 25 | | | | | | | | | | | | | | | |
| * 78008230 | POLYUREA PAVEMENT MARKING TYPE I - LINE 6" | FOOT | 25 | 25 | | | | | | | | | | | | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 50 | 50 | | | | | | | | | | | | | | | |
| * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 50 | 50 | | | | | | | | | | | | | | | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SO FT | 104 | 104 | | | | | | | | | | | | | | | |
| X0325702 | NIGHTTIME WORK ZONE LIGHTING | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| Z0017202 | DOWEL BARS 1 1/2" | EACH | 1820 | 1820 | | | | | | | | | | | | | | | |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | | | | | | | | | | | | | | | |
| Z0075310 | TIE BARS 3/4" | EACH | 190 | 190 | | | | | | | | | | | | | | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 50 | 50 | | | | | | | | | | | | | | | |
| 60603000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-G.12 | FOOT | 50 | 50 | | | | | | | | | | | | | | | |
| | * SPECIALTY ITEM | | | | | | | | | | | | | | | | | | |

Rev.

| | | | | | | | | | | | | | | | | |
|--|-----------------------|------------|--------------------|---|--|--|--|-----------------------|--|--|--|--------------|------------|--------------|---|-----------|
| FILE NAME = | USER NAME = wlgreendp | DESIGNED - | REVISD - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | | | | SUMMARY OF QUANTITIES | | | | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pwwork\FWIDOT\WILGREENDP\0183633\Designdp | DRAWN - | REVISD - | VAR. | | | | | | | | | 2010-021PP | LK. & MCH. | 25 | 3 | |
| PLOT SCALE = 100,000' / 1" IN. | CHECKED - | REVISD - | CONTRACT NO. 60K40 | | | | | | | | | | | | | |
| PLOT DATE = 4/12/2010 | DATE - | REVISD - | SCALE: | | | | | | | | | SHEET NO. OF | SHEETS | STA. TO STA. | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | |