

URBAN
100% STATE

| ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NUMBER |
|---------|------------|--------|--------------|--------------|
| VARIOUS | 2010-027-1 | COOK | 19 | 3 |

CONTRACT NO.: 60K63

| CONSTRUCTION CODE TYPE: SFTY - 1B | | COOK CO. | |
|-----------------------------------|--|----------|------------------|
| CODE NO. | ITEMS | UNITS | TOTAL QUANTITIES |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 91 |
| 42001300 | PROTECTIVE COAT | SQ YD | 1230 |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 54 |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 4087 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 54 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 4087 |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 3273 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 308.4 |
| 44000190 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 546 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 179 |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 179 |

WHEREVER IN THE PLANS THE TERM "HMA SURF R&R FULL DEPTH" IS ENCOUNTERED IT SHALL BE INTERPRETED TO MEAN "HMA SURFACE REMOVAL VARIABLE DEPTH AND REPLACEMENT WITH HMA SURFACE COURSE, MIX D, N 50; DEPTH VARIES 1.5" TO 3"

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev. 6-1-10

Rev.