

URBAN
100% STATE

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2010-027-1	COOK	19	3

CONTRACT NO.: 60K63

CONSTRUCTION CODE TYPE: SFTY - 1B		COOK CO.	
CODE NO.	ITEMS	UNITS	TOTAL QUANTITIES
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	91
42001300	PROTECTIVE COAT	SQ YD	1230
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	51
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4087
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	51
44000600	SIDEWALK REMOVAL	SQ FT	4087
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3259
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	308.4
44000100	PAVEMENT REMOVAL	SQ YD	543
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	179
25200110	SODDING, SALT TOLERANT	SQ YD	179

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev.