

| | | | | |
|--------------|----------------|---------------|---------------------|---------------------|
| ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NUMBER |
| VARIOUS | 2010-027-I | COOK | 19 | 8 |

CONTRACT: 60K63

| LOCATION | COMB. CONC. C & G R&R (LF) | HMA SURF R&R FULL DEPTH (SQ YD) | SIDEWALK 5" R&R (SQ FT) 18" CARRIAGE | SIDEWALK 5" R&R (SQ FT) 5' PARALLEL | DRIVEWAY 8" R&R (SQ FT) | SALT TOLERANT SODDING (SQ YD) | REMARKS |
|---------------------|----------------------------|---------------------------------|--------------------------------------|-------------------------------------|-------------------------|-------------------------------|--------------------|
| 4411 W. 81st St | 10.0 | 1.7 | 0.0 | 50.0 | 0.0 | 0.0 | |
| 4235 W. 81st St | 20.0 | 3.3 | 0.0 | 50.0 | 15.0 | 0.0 | |
| 4211 W. 81st St | 10.0 | 1.7 | 0.0 | 0.0 | 15.0 | 0.0 | |
| 4423 W. 81st St | 5.0 | 0.8 | 0.0 | 25.0 | 0.0 | 0.0 | Adjacent to Sewer |
| 4414 W. 82nd St | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 4336 W. 82nd Place | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 4320 W. 82nd Place | 20.0 | 3.3 | 30.0 | 0.0 | 0.0 | 0.0 | |
| 4314 W. 82nd Place | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | |
| 4308 W. 82nd Place | 15.0 | 2.5 | 22.5 | 0.0 | 0.0 | 0.0 | |
| 4300 W. 82nd Place | 15.0 | 2.5 | 22.5 | 0.0 | 0.0 | 0.0 | |
| 4421 W. 83rd Place | 7.0 | 1.2 | 0.0 | 35.0 | 0.0 | 0.0 | Across from church |
| 4420 W. 83rd St | 50.0 | 8.3 | 0.0 | 250.0 | 0.0 | 0.0 | in front of church |
| 5757 S. Kenton | 15.0 | 2.5 | 0.0 | 0.0 | 0.0 | 2.5 | Side of house |
| 7800 S. Kenton | 18.0 | 3.0 | 0.0 | 0.0 | 0.0 | 3.0 | |
| 8022 S. Kenton | 15.0 | 2.5 | 0.0 | 0.0 | 22.5 | 0.0 | |
| 8028 S. Kenton | 15.0 | 2.5 | 0.0 | 0.0 | 22.5 | 0.0 | |
| 8034 S. Kenton | 8.0 | 1.3 | 12.0 | 0.0 | 0.0 | 0.0 | |
| 8044 S. Kenton | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8048 S. Kenton | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8054 S. Kenton | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | |
| 8060 S. Kenton | 15.0 | 2.5 | 7.5 | 0.0 | 15.0 | 0.0 | |
| 8064 S. Kenton | 11.0 | 1.8 | 16.5 | 0.0 | 0.0 | 0.0 | |
| 8072 S. Kenton | 8.0 | 1.3 | 12.0 | 0.0 | 0.0 | 0.0 | |
| 8086 S. Kenton | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | |
| 8088 S. Kenton | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | |
| 6524 S. Springfield | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 6545 S. Springfield | 7.0 | 1.2 | 10.5 | 0.0 | 0.0 | 0.0 | |
| 6732 S. Springfield | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 6210 S. Tripp | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8204 S. Tripp | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8208 S. Tripp | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8172 S. Tripp | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | |
| 8132 S. Tripp | 10.0 | 1.7 | 15.0 | 0.0 | 0.0 | 0.0 | Yellow paint |
| 8128 S. Tripp | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8122 S. Tripp | 5.0 | 0.8 | 7.5 | 0.0 | 0.0 | 0.0 | |
| 8100 S. Tripp | 15.0 | 2.5 | 22.5 | 0.0 | 0.0 | 0.0 | |
| SUB-TOTAL | 394.0 | 65.7 | 328.5 | 410.0 | 90.0 | 5.5 | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES