

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	4
STA. 12+06.00		TO STA.16+17.11		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PROJECT LOCATION: FAI 57 AT GENOA AVENUE
COOK COUNTY

CODE NUMBER	ITEM	UNIT	100% STATE		
			TOTAL QUANTITY URBAN	ROADWAY 1000-2A	BRIDGE X271-2A
20101000	TEMPORARY FENCE	FOOT	80	80	
20101200	TREE ROOT PRUNING	EACH	1	1	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	1	1	
20200100	EARTH EXCAVATION	CU YD	109	109	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100	
20800150	TRENCH BACKFILL	CU YD	10	10	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	898	898	
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	17	17	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	17	17	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	17	17	
25100630	EROSION CONTROL BLANKET	SQ YD	898	898	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	19	19	
28000400	PERIMETER EROSION BARRIER	FOOT	374	374	
28000510	INLET FILTERS	EACH	6	6	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	156	156	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	66	66	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	87	87	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	13	13	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	99	99	
42001300	PROTECTIVE COAT	SQ YD	414	414	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	70	70	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,661	1,661	
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	363	363	
44000100	PAVEMENT REMOVAL	SQ YD	187	187	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1173	1173	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	422	422	
44000600	SIDEWALK REMOVAL	SQ FT	465	465	
44000700	APPROACH SLAB REMOVAL	SQ YD	234	234	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	60	60	
44003100	MEDIAN REMOVAL	SQ FT	85	85	
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	30	30	
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	30	30	

* SPECIALTY ITEM

PLOT DATE = Monday, March 08, 2010
FILE NAME = S:\11-CADD\01-11\11-04-07_106000.dgn
PLOT SCALE = 50:1
USER NAME = j3679



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 1 OF 4
GENOA AVENUE OVER FAI-57

SCALE: VERT. NONE
HORIZ.
DATE: 3/1/2010

DRAWN BY: E.D.
CHECKED BY: A.A.C.