

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	5
STA. 12+06.00		TO STA. 16+17.11		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PROJECT LOCATION: FAI 57 AT GENOA AVENUE  
COOK COUNTY

CODE NUMBER	ITEM	UNIT	100% STATE		
			TOTAL QUANTITY URBAN	ROADWAY 1000-2A	BRIDGE X271-2A
50102400	CONCRETE REMOVAL	CU YD	67		67
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50157300	PROTECTIVE SHIELD	SQ YD	1143		1143
50200100	STRUCTURE EXCAVATION	CU YD	56		56
50300225	CONCRETE STRUCTURES	CJ YD	59.6		59.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	729.8		729.8
50300280	BRIDGE DECK GROOVING	SQ YD	1,425		1,425
50300300	PROTECTIVE COAT	SQ YD	2,244		2,244
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4,640		4,640
50500505	STUD SHEAR CONNECTORS	EACH	4,368		4,368
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28		28
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	135,110		135,110
50800515	BAR SPLICERS	EACH	813		813
50901730	BRIDGE FENCE RAILING	FOOT	562		562
51205200	TEMPORARY SHEET PILING	SQ FT	233		233
51500100	NAME PLATES	EACH	2		2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	143		143
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28		28
52100520	ANCHOR BOLTS, 1"	EACH	56		56
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	51	51	
55039700	STORM SEWERS TO BE CLEANED	FOOT	607	607	
58700300	CONCRETE SEALER	SQ FT	853		853
59000200	EPOXY CRACK INJECTION	FOOT	126		126
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5	
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60600605	CONCRETE CURB, TYPE B	FOOT	131	131	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	141	141	
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	282	282	
66400105	CHAIN LINK FENCE, 4'	FOOT	40	40	
66410300	CHAIN LINK FENCE REMOVAL	FOOT	40	40	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	210	210	

\* SPECIALTY ITEM

PLOT DATE = Monday, March 08, 2010  
FILE NAME = S:\11-CADD\11-11-10\11-04-07-980.dwg  
PLOT SCALE = 50%  
USER NAME = 3696



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
SHEET 2 OF 4  
**GENOA AVENUE OVER FAI-57**

SCALE: VERT. NONE  
HORIZ.  
DATE: 3/1/2010

DRAWN BY: E.D.  
CHECKED BY: A.A.C.