


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	6
STA. 12+06.00		TO STA.16+17.11		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PROJECT LOCATION: FAI 57 AT GENOA AVENUE
COOK COUNTY

CODE NUMBER	ITEM	UNIT	100% STATE		
			TOTAL QUANTITY URBAN	ROADWAY 1000-2A	BRIDGE X271-2A
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	834	834	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	36	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	514	514	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	725	725	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	278	278	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	975	975	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	250	250	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	13	13	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	19	19	
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2	2	
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	300	300	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	769	769	
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	820	820	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	45	45	
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	79	79	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	82	82	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	108	108	
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	100		100
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	210		210
* 81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	140		140
* 81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	1148		1148
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	650		650
* 81200250	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	20		20
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8		8
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	4		4
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	4		4
* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	94		94
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1,100		1,100
* 81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	138		138
* 81700125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	413		413
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	600		600
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	440		440
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	8		8
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	12		12
* 87900100	DRILL EXISTING FOUNDATION	EACH	4		4

* SPECIALTY ITEM
** NON-PARTICIPATING ITEM
*** FUND CODE: SFTY 3N

PLOT DATE = Monday, March 05, 2010
FILE NAME = S:\11-CADD\11-10-10-01-07-956cse01.dgn
PLOT SCALE = 50%
USER NAME = J5910



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 3 OF 4
GENOA AVENUE OVER FAI-57

VERT. NONE
SCALE: HORIZ.
DATE: 3/1/2010
DRAWN BY: E.D.
CHECKED BY: A.A.C.