

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	11
STA. 12+06.00		TO STA.16+17.11		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

WET REFLECTIVE TEMPORARY TAPE, TYPE III - LINE 6 INCH (FT)
POLYUREA PAVEMENT MARKING - LINE 6" (FT)

BEGIN STA	END STA	LENGTH	NOTES
12+47	12+52	105.7	GENOA AVE CROSSWALK
12+62	12+95	66.4	N 98TH PLACE CROSSWALK
12+55	12+93	73.3	S 98TH PLACE CROSSWALK
13+21	15+44	223.0	E/B GENOA LANE LINE
13+21	15+44	223.0	W/B GENOA LANE LINE
51+65	51+71	62.2	S RACINE AVE CROSSWALK
52+28	52+34	66.4	N RACINE AVE CROSSWALK
TOTAL = 820 FT			

WET REFLECTIVE TEMPORARY TAPE, TYPE III - LINE 24 INCH (FT)

BEGIN STA	LENGTH	NOTES
12+04	25.0 FT	GENOA AVE STOP BAR STAGE 1
12+00	15.1 FT	GENOA AVE STOP BAR STAGE 2
PRIOR TO PERMANENT MARKINGS		
BEGIN STA	LENGTH	NOTES
12+10	28.8	W/B GENOA AVE STOP BAR
12+80	20.4	S/B 98TH PLACE STOP BAR
15+61	29.9	N/B RACINE AVE STOP BAR
TOTAL = 119 FT		

POLYUREA PAVEMENT MARKING - LINE 12" (FT)

BEGIN STA	END STA	LENGTH	NOTES
12+16	12+63	44.7 FT	MEDIAN DIAGONALS
TOTAL = 45 FT			

WET REFLECTIVE TEMPORARY TAPE, TYPE III - LINE 4 INCH (FT)

BEGIN STA	END STA	LENGTH	NOTES
9+40	10+12	72.7 FT	YELLOW, E/B MOT STAGE 1
9+40	12+04	266.8 FT	YELLOW, E/B MOT STAGE 1
10+98	12+04	111.1 FT	YELLOW, W/B MOT STAGE 1
10+00	12+68	344.7 FT	WHITE, E/B MOT STAGE 1
12+04	12+58	56.0 FT	DOUBLE YELLOW, MOT STAGE 1
9+40	12+38	288.0 FT	YELLOW, E/B MOT STAGE 2
11+40	12+38	96.6 FT	YELLOW, W/B MOT STAGE 2
12+38	12+56	17.3 FT	DOUBLE YELLOW, MOT STAGE 2
11+94	12+68	225.4 FT	WHITE, W/B MOT STAGE 2
13+17	15+82	529.3 FT	DOUBLE YELLOW STAGE 2
PRIOR TO PERMANENT MARKINGS			
BEGIN STA	END STA	LENGTH	NOTES
13+21	15+44	446 FT	CENTERLINE DOUBLE YELLOW
12+06	12+68	251 FT	MEDIAN DOUBLE YELLOW
12+23	12+33	48 FT	99TH STREET SKIP-DASH
51+32	51+42	12 FT	RACINE SKIP DASH
52+33	52+83	12 FT	RACINE SKIP DASH
TOTAL = 2,777 FT			

POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)

STATION	OFFSET	SQ FT	NOTES
13+32	6.5 RT	22.9	ONLY
13+32	17.4 RT	22.9	ONLY
13+34	7.9 LT	15.8	LT ARROW
13+34	17.7 LT	11.2	STR ARROW
13+55	18.0 RT	15.8	LT ARROW
13+55	6.6 RT	15.8	LT ARROW
13+58	6.3 LT	22.9	ONLY
13+59	17.7 LT	22.9	ONLY
15+08	6.5 RT	22.9	ONLY
15+08	17.4 RT	22.9	ONLY
15+10	7.9 LT	15.8	LT ARROW
15+10	17.7 LT	11.2	STR ARROW
15+33	18.0 RT	15.8	LT ARROW
15+33	6.6 RT	15.8	LT ARROW
15+33	6.3 LT	22.9	ONLY
15+34	17.7 LT	22.9	ONLY
TOTAL = 300 SQ FT			

POLYUREA PAVEMENT MARKING - LINE 24" (FT)

LOCATION	LENGTH	NOTES
12+10	28.8	W/B GENOA AVE STOP BAR
12+80	20.4	S/B 98TH PLACE STOP BAR
15+61	29.9	N/B RACINE AVE STOP BAR
TOTAL = 79 FT		

PAVEMENT MARKING REMOVAL (SQ FT)

BEGIN STA	END STA	WIDTH	SQ FT	NOTES
12+06	15+90	4 IN	34.0	W/B GENOA SKIP-DASH
12+09		24 IN	58.0	W/B GENOA STOP BAR
9+50	12+06	4 IN	16.0	E/B 99TH ST SKIP-DASH
TOTAL = 108 SQ FT				

WET REFLECTIVE TEMPORARY TAPE, TYPE III - LINE 12 INCH (FT)

BEGIN STA	END STA	LENGTH	NOTES
9+40	12+04	88.8 FT	YELLOW, E/B MOT STAGE 1
9+40	12+38	219.4 FT	YELLOW, E/B MOT STAGE 2
PRIOR TO PERMANENT MARKINGS			
BEGIN STA	END STA	LENGTH	NOTES
12+16	12+63	44.7 FT	MEDIAN DIAGONALS
TOTAL = 353 FT			

POLYUREA PAVEMENT MARKING - LINE 4" (FT)

BEGIN STA	END STA	LENGTH	NOTES
13+21	15+44	446 FT	CENTERLINE DOUBLE YELLOW
12+06	12+68	251 FT	MEDIAN DOUBLE YELLOW
12+23	12+33	48 FT	99TH STREET SKIP-DASH
51+32	51+42	12 FT	RACINE SKIP DASH
52+33	52+83	12 FT	RACINE SKIP DASH
TOTAL = 769 FT			

PLOT DATE = Thursday, March 04, 2010
 FILE NAME = S:\11-CADD\11-11-09-ILL 589\c101.dgn
 PLOT SCALE = 50:1
 USER NAME = 3879



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
SHEET 3 OF 3
GENOA AVENUE OVER FAI-57

SCALE: VERT. NONE
 HORIZ. NONE
 DATE: 3/1/2010

DRAWN BY: E.D.
 CHECKED BY: A.A.C.