

# SUMMARY OF QUANTITIES

CODE NO	PAY ITEM	UNIT	ROADWAY (1000)
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	40
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	40
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1121
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1121
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2153
25200110	SODDING, SALT TOLERANT	SQ YD	2153
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	23
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6726
40600300	AGGREGATE (PRIME COAT)	TON	135
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3767
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	370
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	518
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6592
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3700
42400800	DETECTABLE WARNINGS	SQ FT	75
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	67260
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	80
44000600	SIDEWALK REMOVAL	SQ FT	3700
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	850
44002211	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 3/4"	SQ YD	3364
44201325	CLASS C PATCHES, TYPE I, 8 INCH	SQ YD	425
44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	425
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ YD	425
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	425
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	416
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	416
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	416
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	416
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5100

CODE NO	PAY ITEM	UNIT	ROADWAY (1000)
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	28
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4700
△	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	1550
△	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	4700
△	TEMPORARY PAVEMENT MARKING LINE 6"	FOOT	7116
△	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	2562
△	TEMPORARY PAVEMENT MARKING LINE 24"	FOOT	745
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12294
△	78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1550
△	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4700
△	78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7116
△	78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2562
△	78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	745
△	88600600 DETECTOR LOOP REPLACEMENT	FOOT	3000
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	5
* Z0076600	TRAINEES	HOUR	500

△ DENOTE SPECIALTY ITEMS

\* Y080

FILE NAME = D:\Naper\11e12245876\_095\h Street\_LRP\Roadway\_Quantity\_Summary.dgn



USER NAME = #USER#  
 DESIGNED - KM  
 DRAWN - KM  
 CHECKED - MHL  
 DATE - 3/1/10

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

## SUMMARY OF QUANTITIES

SCALE: 1" = ft SHEET NO. 3 OF SHEETS STA. TO STA.

F.A.U. RTE. 1644	SECTION 09-00142-00-RS	COUNTY WILL	TOTAL SHEETS 22	SHEET NO. 3
CONTRACT NO. 63244				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				