

	NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000-2A QTY
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	79	79
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	10	10
	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	12	12
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,216	1,216
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	714	714
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	191	191
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,116	1,116
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	63	63
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	560	560
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	544	544
	55101200	STORM SEWER REMOVAL 24"	FOOT	230	230
	55101600	STORM SEWER REMOVAL 36"	FOOT	20	20
	552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	215	215
+	56300300	ADJUSTING WATER SERVICE LINES	FOOT	40	40
+	56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	1	1
	60107600	PIPE UNDERDRAINS 4"	FOOT	90	90
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
	60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	7	7
	60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	22	22
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1
	60204805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	10	10
	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
	60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
	60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1
	60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	2	2
	60224020	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2	2
	60224448	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 8 GRATE	EACH	1	1
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	17	17
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10
*	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8
	60500040	REMOVING MANHOLES	EACH	6.0	6.0
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8	8
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,994	5,994
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	374	374
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	150	150
	60620321	CONCRETE MEDIAN, TYPE SB-8.06	SQ FT	1,190	1,190
+	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	425	425

+ INDICATES SPECIALTY ITEMS

* INDICATES SPECIAL PROVISION

	NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000-2A QTY
+	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
+	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
*	63200310	GUARD RAIL REMOVAL	FOOT	382	382
*	66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	283	283
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	3	3
	67100100	MOBILIZATION	L SUM	1	1
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	15	15
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,000	5,000
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	306	306
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21,743	21,743
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,274	1,274
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	602	602
	70300270	TEMPORARY PAVEMENT MARKING - LINE 16"	FOOT	88	88
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	272	272
	70300520	PAVEMENT MARKING TAPE, TYPE III 4	FOOT	1,300.00	1,300.00
	72000100	SIGN PANEL - TYPE 1	SQ FT	27.25	27.25
	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	16.3	16.3
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	114	114
	72900110	METAL POST - TYPE A	EACH	33	33
	72900210	METAL POST - TYPE B	EACH	1	1
+	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	306	306
+	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21,743	21,743
+	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,274	1,274
+	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	602	602
+	78000610	THERMOPLASTIC PAVEMENT MARKING - LINE 16"	FOOT	88	88
+	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	272	272
+	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	289	289
+	78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6
+	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2
*	78300100	PAVEMENT MARKING REMOVAL	SQ FT	8,625	8,625
+	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1	1

FILE NAME = S:\JUL_6600-6697\6628\084\Micros\Sheets\summaryofquantities.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = raymondk
PLOT SCALE = 20,000' / IN.
PLOT DATE = 3/31/2012

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.J.
RTE. 3759

SECTION
04-00038-00-WR

COUNTY
WILL

TOTAL SHEETS
165

SHEET NO.
5

CONTRACT NO. 63248

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT