


SIGNS													
EXISTING LOCATION	PROPOSED LOCATION					72000100	72400310	72400710	72900110	72900210	Z0051500		
STATION	OFFSET	STATION	OFFSET	DESCRIPTION	MUTCD CODE	SIGN PANEL - TYPE 1	REMOVE SIGN PANEL -TYPE 1	RELOCATE SIGN PANEL -TYPE 1	METAL POST - TYPE A	METAL POST - TYPE B	REM. AND RESET STREET SIGNS		
				FT		SQ FT	SQ FT	SQ FT	EACH	EACH	EACH		
CENTER ROAD													
104+55	19.8 LT	104+55	23.4 LT	NO PARKING BETWEEN SIGNS (RIGHT ARROW)	R7-1			1.5	1				
105+12	19 RT	105+12	24.6 RT	NO PARKING BETWEEN SIGNS (LEFT ARROW)	R7-1			1.5	1				
105+98	19.4 LT	105+98	25.7 LT	NO PARKING ANYTIME	R7-1			1.5	1				
105+98	20.2 RT	105+98	25.9 RT	NO PARKING ANYTIME	R7-1			1.5	1				
107+54	19.3 LT	107+54	28.1 LT	NO PARKING ANYTIME	R7-1			1.5	1				
108+36	24.9 LT	108+36	26.1 LT	SPEED LIMIT 45 MPH	R2-1			5	1				
109+18	19.3 LT	109+10	32.2 LT	NO PARKING BETWEEN SIGNS (LEFT ARROW)	R7-1			1.5	1				
109+39	27.6 RT	109+46	38.5 RT	STOP SIGN, ALL WAY	R1-1, R1-4			7	1				
110+55	29.9 LT	110+55	31.0 LT	STOP SIGN, ALL WAY	R1-1, R1-4			7	1				
113+26	22.9 RT	113+26	20.2 RT	SPEED LIMIT 45 MPH	R2-1			5	1				
116+81	52.8 RT	116+91	36.4 RT	STOP SIGN	R1-1, R1-4			6.25	1				
116+94	34 RT	116+94	34.4 RT	FRANKFORT STREET SIGNS				2					
117+55	21.1 LT			STOP AHEAD	W3-1		9						
129+04	20.2 LT	129+04	20.2 LT	SPEED LIMIT 45 MPH	R2-1			5	1				
129+06	20.1 RT	129+06	20.1 RT	SPEED LIMIT 35 MPH	R2-1			5	1				
134+90	16.8 RT	134+90	20.33 RT	WEIGHT LIMIT 3 TONS, SNOW PARKING	R7-203, R12-1	5	5	5	1				
135+95	21.3 RT	135+95	20.2 RT	HIGHWAY-RAIL GRADE CROSSING ADVANCE WARNING	W10-1				1				
136+17	39.7 LT	136+20	36.9 LT	STOP SIGN/FRANKFORT STREET SIGN/CUSTOM SIGN	R1-1			9					
		136+66	2.5 LT	KEEP RIGHT	R4-7	5			1				
137+16	19.2 RT	137+16	18.7 RT	NOTICE-INCREASE TRAIN TRAFFIC				1	1				
		137+58	0 RT	KEEP RIGHT	R4-7	5			1				
		137+88	0 RT	KEEP RIGHT	R4-7	5			1				
		138+83	0.2 RT	KEEP RIGHT	R4-7	5			1				
139+15	18 RT	139+15	18.7 RT	SPEED LIMIT 25 MPH	R2-1			5	1				
139+81	18.7 RT	139+81	19.5 RT	SCHOOL BUS STOP AHEAD	S3-1			6.25		1			
149+66	25.9 LT	149+66	25.9 LT	EXIT ONLY		2.25	2.25		1				
LARAWAY ROAD													
206+97	21.6 LT	206+97	28.97 LT	SPEED LIMIT 40 MPH	R2-1			5	1				
207+69	22.4 RT	207+69	27.3 RT	AIRPORT, ARROW	I-5			4	1				
209+40	14.9 RT	209+23	27.8 RT	STOP SIGN, ALL WAY	R1-1, R1-4			7	1				
209+44	37.4 RT	209+44	37.4 RT	FRANKFORT STREET SIGNS									1
210+48	21.8 LT	210+47	35.2 LT	STOP SIGN, ALL WAY	R1-1, R1-4			7	1				
210+70	22.8 LT	210+70	32.0 LT	NO PARKING BETWEEN SIGNS (RIGHT ARROW)	R7-1			1.5	1				
210+87	26.9 RT	210+87	34.8 RT	NO PARKING BETWEEN SIGNS (LEFT ARROW)	R7-1			1.5	1				
212+30	21.1 LT	212+30	30.8 LT	NO PARKING ANYTIME	R7-1			1.5	1				
212+47	20.3 LT	212+47	30.8 LT	AIRPORT, ARROW	I-5			4	1				
213+89	24.6 RT	213+89	27.2 RT	NO PARKING ANYTIME	R7-1			1.5	1				
213+90	23.3 LT	213+90	30.2 LT	NO PARKING ANYTIME	R7-1			1.5	1				
215+48	22.6 LT	215+48	26.4 LT	NO PARKING BETWEEN SIGNS (LEFT ARROW)	R7-1			1.5	1				
TOTAL						27.25	16.25	113.5	33	1		1	

GUARD RAIL		63200310		63000001		63100167		63100045		
LOCATION (STATION)	OFFSET	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2					
FROM	TO	FOOT	FOOT	EACH	EACH					
LARAWAY ROAD										
211+87.50										1
212+00	216+25	LT				425				
216+25		LT						1		
212+82	215+14	LT	232.00							
213+48	215+00.00	RT	150.00							
TOTAL			382			425		1		1

ROW MARKERS		
PROPOSED LOCATION	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
STATION	OFFSET	EACH
	FT	
109+10.3	40.0 LT	1
109+35.3	64.9 LT	1
109+60.3	90.0 LT	1
TOTAL		3



SIDEWALK				44004600		42400800		31101200	
BEGINNING STATION	OFFSET	LENGTH	WIDTH	SIDEWALK REMOVAL AND REPLACEMENT	DETECTABLE WARNINGS	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SQ FT	SQ FT	SQ YD
				FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ YD
113+55	LT	5	5	25	9	2.8			
113+98	LT	5	5.5	28	9	3.1			
115+97	LT	5	5	25	9	2.8			
116+29	LT	5.5	5.5	30	9	3.4			
141+25	RT	4	5	20	9	2.2			
141+32	RT	4	5	20	9	2.2			
141+75	RT	4	5	20	9	2.2			
141+83	RT	4	5	20	9	2.2			
143+50	LT	4	195	780	18	86.7			
145+07	RT	4	40	160		17.8			
147+58	RT	4	40	160		17.8			
148+45	RT	4	250	1,000	36	111.1			
149+64	LT	4	53	212	9	24.0			
148+94	LT	4	53	212	9	23.6			
151+13	LT	4	5	20	9	2.2			
151+26	LT	4	5	20	9	2.2			
TOTAL				2,752	162	306			

DRIVEWAYS												
LOCATION (CENTERLINE STATION)	OFFSET	A	B	C	44000200	Z0004530	Z0004538	42300400	40200800	X4021000	X4022000	3110100
		FOOT	FOOT	FOOT	DRIVEWAY PAVEMENT REMOVAL	HOT-MIX ASPHALT DRIVEWAY PAVEMENT 8"	HOT-MIX ASPHALT DRIVEWAY PAVEMENT 10"	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8"	AGGREGATE SURFACE COURSE, TYPE B (CA-6)	TEMPORARY ACCESS (PRIVATE ENTRANCE)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	SUBBASE GRANULAR MATERIAL, TYPE B, 6"
					SQ YD	SQ YD	SQ YD	SQ YD	TON	EACH	EACH	SQ YD
CENTER ROAD												
104+41	RT	56	33	32	233							133
107+06	RT	48	26	29	117							100
112+19	RT	24	21	15					28			
116+75	LT	52	22	12	87	50				1		50
118+54	RT	51	22	30	208		89				1	89
119+23	LT	27	16	18					33			
119+82	RT	53	22	28	202		89				1	89
123+01	RT	21	16	11.5					22			
123+91	RT	67	22	42	259		128				1	128
127+07	RT	60	22	35	167		100				1	100
128+64	RT	24	16	15					29			
132+58	RT	46	21	28	138		72				1	72
133+14	LT	46	22	24	126		74				1	74
133+49	RT	53	20	33	181		92				1	92
133+87	LT	51	22	29	160			85			1	
134+34	RT	61	21	37	167						1	114
135+38	LT	54	22	30	115		88				1	88
135+44	RT	51	21	34	306		89				1	89
137+00	LT								52			
LARAWAY ROAD												
207+86	RT	37	17	17					28			
211+64	LT	40	28	21	88	70				1		70
211+69	RT	72	27	42	167		127				1	127
212+92	RT	84	28	33	150		142				1	142
TOTAL					2,871	120	1,437	85	192	2	15	1,557

* AREA NEAR TRACKS IS NOT A DRIVEWAY
DIMENSIONS 'A', 'B', AND 'C' REPRESENT THE PROPOSED DRIVEWAY WIDTHS

FILE NAME = s:\j\166800-66899\6629\084\mcrca\sheet\scheduleofquantities.dgn

 1170 SOUTH HOBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = adamm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 20.0000' / 1" IN.	CHECKED -	REVISED -			3759	04-00038-00-WR	WILL	165	12
	PLOT DATE = 3/31/2012	DATE	REVISED -	SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
						CONTRACT NO. 63248				