

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS 78000100				
LOCATION (STATION)	OFFSET	COLOR	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT
STATION	ROADWAY			
107+82	CENTER	CL	WHITE	20.8
108+07	CENTER	CL	WHITE	15.6
111+99	CENTER	CL	WHITE	15.6
112+25	CENTER	CL	WHITE	20.8
117+61	CENTER	CL	WHITE	15.6
117+87	CENTER	CL	WHITE	20.8
135+17	CENTER	CL	WHITE	20.8
135+43	CENTER	CL	WHITE	15.6
134+50	CENTER	RT	WHITE	3.6
134+50	CENTER	RT	WHITE	3.6
135+15	CENTER	CL	WHITE	20.8
135+40	CENTER	CL	WHITE	15.6
140+90	CENTER	LT	WHITE	3.6
140+90	CENTER	LT	WHITE	3.6
206+95	LARAWAY	CL	WHITE	20.8
207+25	LARAWAY	CL	WHITE	15.6
208+80	LARAWAY	CL	WHITE	20.8
209+09	LARAWAY	CL	WHITE	15.6
211+50	LARAWAY	CL	WHITE	15.6
211+80	LARAWAY	CL	WHITE	20.8
TOTAL				306

THERMOPLASTIC PAVEMENT MARKING - LINE 24" 78000650				
LOCATION (STATION)	OFFSET	COLOR	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT
FROM	TO			
CENTER ROAD				
109+54		CL/RT	WHITE	33
110+52		CL/LT	WHITE	26
116+58		RT	WHITE	28
134+25		RT	WHITE	11
134+75		RT	WHITE	11
136+24		LT	WHITE	14
137+40		RT	WHITE	11
138+02		LT	WHITE	11
140+65		LT	WHITE	15.5
141+15		LT	WHITE	15.5
141+56		RT	WHITE	17
150+96		RT	WHITE	23
LARAWAY ROAD				
209+25		RT/CL	WHITE	28
210+45		LT/CL	WHITE	28
TOTAL				272

THERMOPLASTIC PAVEMENT MARKING - LINE 12" 78000600				
LOCATION (STATION)	OFFSET	COLOR	TYPE	THERMOPLASTIC PAVEMENT MARKING - LINE
FROM	TO			FOOT
CENTER ROAD				
104+00	107+30	CL	YELLOW DIAGONAL	127
107+70	109+80	RT	WHITE DIAGONAL	44
108+98	109+72	LT	WHITE DIAGONAL	22
110+22	115+68	LT	WHITE DIAGONAL	82
110+20	110+80	RT	WHITE DIAGONAL	17
112+97	116+20	CL	YELLOW DIAGONAL	219
118+40	134+74	CL	YELLOW DIAGONAL	63
138+86	139+71	CL	YELLOW DIAGONAL	28
LARAWAY ROAD				
204+32	206+76	CL	YELLOW DIAGONAL	131
212+05	216+23	CL	YELLOW DIAGONAL	209
TOTAL				602

THERMOPLASTIC PAVEMENT MARKING - LINE 6" 78000400				
LOCATION (STATION)	OFFSET	COLOR	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT
FROM	TO			
CENTER ROAD				
107+69	109+54	RT	WHITE	185
110+52	112+37	LT	WHITE	185
116+87	118+02	LT	WHITE	115
133+80	134+25	RT	WHITE	12
134+25	134+75	RT	WHITE	50
134+75	135+01	RT	WHITE	8
135+01	136+16	RT	WHITE	115
141+36	141+74	RT	WHITE	74
150+96	151+11	RT/LT	WHITE	44
151+00	151+24	RT	WHITE	24
151+03	151+26	RT	WHITE	24
151+02	151+17	RT/LT	WHITE	43
151+31	151+41	LT	WHITE	10
LARAWAY ROAD				
206+84	209+25	RT	WHITE	240
210+47	211+92	CL	WHITE	145
TOTAL				1,274

THERMOPLASTIC PAVEMENT MARKING - LINE 4" 78000200				
LOCATION (STATION)	OFFSET	COLOR	TYPE	THERMOPLASTIC PAVEMENT MARKING - LINE 4"
FROM	TO			FOOT
CENTER ROAD				
102+40	103+00	CL	YELLOW DOUBLE	120
102+40	109+80	LT	WHITE	770
103+00	109+54	LT/CL	YELLOW DOUBLE	1,310
103+00	107+69	RT/CL	YELLOW DOUBLE	940
102+40	109+80	RT		776
107+70	109+80	RT		53
110+20	111+26	RT	WHITE	117
110+27	116+04	LT	WHITE	584
110+52	116+29	RT	YELLOW DOUBLE	1,152
112+38	116+29	LT	YELLOW DOUBLE	792
116+88	135+01	RT	YELLOW DOUBLE	3,632
118+02	136+16	LT	YELLOW DOUBLE	3,640
136+60	137+60	RT	YELLOW	103
136+60	137+60	LT	YELLOW	103
137+82	138+86	RT	YELLOW	104
137+82	138+86	LT	YELLOW	104
138+86	140+08	RT	YELLOW DOUBLE	246
138+86	140+05	LT	YELLOW DOUBLE	238
140+08	141+26	CL	YELLOW DOUBLE	238
141+97	151+00	CL	YELLOW SKIP-DASH	226
LARAWAY ROAD				
204+02	209+32	RT	WHITE	530
204+02	209+24	RT	YELLOW DOUBLE	1,046
204+02	209+24	LT	YELLOW DOUBLE	1,044
204+32	209+48	LT	WHITE	515
210+47	217+30	RT	YELLOW DOUBLE	1,368
210+47	217+00	LT	YELLOW DOUBLE	1,310
210+49	217+30	LT	WHITE	682
TOTAL				21,743

PAVEMENT MARKING REMOVAL 78300105			
LOCATION (STATION)	OFFSET	STREET	PAVEMENT MARKING REMOVAL
FROM	TO		FOOT
102+40	106+70	CENTER	968
110+50	137+50	CENTER	3,375
204+30	207+50	LARAWAY	1,672
207+50	209+40	LARAWAY	570
210+50	217+30	LARAWAY	2,040
TOTAL			8,625

THERMOPLASTIC PAVEMENT MARKING - LINE 16" 78000610				
LOCATION (STATION)	OFFSET	COLOR	THERMOPLASTIC PAVEMENT MARKING - LINE 16"	FOOT
FROM	TO			
134+50		RT	WHITE	44
140+90		LT	WHITE	44
TOTAL				88

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT 40600980		
LOCATION (STATION AT CENTERLINE OF CENTER ROAD)	OFFSET	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
		SQ YD
102+40	CL	84
103+06	RT	50
113+79	LT	41
116+15	LT	27
116+50	LT	40
136+45	LT	27
137+30	LT	78
137+82	LT	15
141+50	RT	39
151+07	CL	160
LARAWAY ROAD		
204+02	CL	172
212+92	RT	74
216+66	RT	44
217+00	CL	87
TOTAL		936

FILE NAME = s:\j\166280 - 68991662800A.mxd, sheet 43, schedule of quantities.dgn



1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
(815) 744-4200

USER NAME = adam  
PLOT SCALE = 20.0000" / IN.  
PLOT DATE = 3/31/2012

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3759	04-00038-00-WR	WILL	165	13
CONTRACT NO. 63248				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				