HOT-MIX ASPHALT MIXTURE REQUIREMENTS NOTES:

CONTRACTOR SHALL MILL BEFORE PATCHING.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS


MIXTURE TYPE .	AIR VOIDS @ Ndes
RESURFACING	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL 9,5mm)	4% © 50 GYR.
POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75mm, N50	4% @ 50 GYR.
PATCHING	
CLASS D PATCHES (HMA BINDER IL-19 mm) - 7-INCH & 3-INCH (SPECIAL)	4% © 70 GYR.

THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX ASPHALT SURFACE MIXTURES IS 112 LBS/SQ. YD./IN

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 70-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY THE DISTRICT ONE SPECIAL PROVISIONS. FOR "PERCENT RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.

OLD CHECKER ROAD EX ROW EX ROW 1.5' 12' & VARIES 12' & VARIES 1.5' 32' E-E VARIES 2.0% & VARIES 2.0% & VARIES

EXISTING TYPICAL SECTION OLD CHECKER ROAD STA. 10 + 16 TO STA. 51 + 89



EXISTING LEGEND

(A)	HCT-MIX ASPHALT SURFACE AND BINDER COURSE, 3"
B	HOT-MIX ASPHALT BASE COURSE, 6"
(C)	AGGREGATE SUB-BASE, 6"
0	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
E	SIDEWALK
(F)	GROUND SURFACE
J	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"
	ITEM TO BE REMOVED

SCALE:

PROPOSED LEGEND

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 - 2" POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 - 3/4" COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (AS SHOWN ON PLANS OR AS DETERMINED BY THE ENGINEER) CLASS D PATCHES, TYPE II-IV, 7" (AS DETERMINED BY THE ENGINEER) CLASS D PATCHES, 3" (SPECIAL) (AS DETERMINED BY THE ENGINEER) AGGREGATE BASE COURSE, TYPE B - 4" (AS REQUIRED) PORTLAND CEMENT CONCRETE SIDEWALK - 5" (SEE NOTE 1)

LEGEND NOTES:

1. LOCATIONS OF SIDEWALK REMOVAL AND PCC SIDEWALK - 5" TO BE AS SHOWN ON PLANS OR AS DETERMINED BY THE ENGINEER.



1	DESIGNED	-	DSH	REVISED-10-09-09 PER IDOT REVIEW
	DRAWN	-	KAR	REVISED -
	CHECKED	-	RWL	REVISED
	DATE	-	10-09-09	FILE - 090715-typ sec.sht

TYPICAL SECTIONS AND HMA MIXTURE REQUIREMENTS			F.A.U. RTE.	SECTION	COUNTY	TOTAL	SHEE
			1268	09-00098-00-RS	LAKE	21	4
				C-91-884-09		CONTRACT NO. 6333	
	STA. 10+00	TO STA. 20+50	FED. ROA	D DIST. NO. ILLINOIS FED.	AID PROJECT ARA	A-9003(453	i)