


6 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70							
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	AVERAGE WIDTH (FEET)	DEPTH (INCHES)	AREA TO BE PRIMED (SQ. YDS.)	QUANTITY (TONS)
MAINLINE - LEFT							
1+58	3+22	LT	164.0	36.0	2.0	654.0	73.2
3+22	5+25	LT	203.0	28.0	2.0	632.0	70.8
5+25	7+42	LT	217.0	25.0	1.5	597.0	50.1
7+42	11+23	LT	381.0	17.5	1.5	742.0	62.3
11+23	22+25	LT	1102.0	11.0	1.5	1347.0	113.1
22+25	24+64	LT	239.0	19.0	1.5	506.0	42.5
24+64	28+00	LT	336.0	11.0	1.5	411.0	34.5
28+00	50+10	LT	2199.2*	11.0	1.5	2680.9	225.2
65+04	67+88	LT	284.0	11.0	1.5	346.0	29.1
84+25	165+80	LT	8131.61*	11.0	1.5	9939.0	834.9
184+25	187+66	LT	341.0	16.0	1.5	611.0	51.3
						18465.9	1587.1
MAINLINE - RIGHT							
1+58	2+62	RT	104.0	17.0	2.0	200.0	22.4
2+62	5+25	RT	263.0	11.5	2.0	340.0	38.1
5+25	7+42	RT	217.0	14.0	1.5	334.0	28.1
7+42	22+25	RT	1483.0	11.0	1.5	1872.0	157.2
22+25	28+00	RT	575.0	11.0	1.5	702.0	59.0
28+00	39+50	RT	1150.0	11.0	1.5	1412.0	118.6
39+50	40+61	RT	100.2*	15.0	1.5	183.0	15.4
40+61	42+33	RT	172.0	21.0	1.5	405.0	34.0
42+33	50+10	RT	777.0	11.0	1.5	949.9	79.8
65+04	67+88	RT	284.0	11.0	1.5	346.0	29.1
84+25	165+80	RT	8131.61*	11.0	1.5	9940.0	835.0
184+25	187+66	RT	341.0	20.0	1.5	748.0	62.8
						17431.9	1479.4
MAINLINE SHOULDER- LEFT							
7+42	22+41	LT	1499.0	4.0	1.5	657.0	55.2
24+64	28+00	LT	336.0	2.0	1.5	75.0	6.3
28+00	47+20	LT	1909.2*	4.0	1.5	843.0	70.8
47+20	47+40	LT	20.0	6.0	1.5	13.0	1.1
47+40	47+60	LT	20.0	8.0	1.5	18.0	1.5
47+60	47+90	LT	30.0	6.0	1.5	20.0	1.7
47+90	50+10	LT	225.0	4.0	1.5	97.8	8.2
65+04	66+52	LT	148.0	4.0	1.5	61.0	5.1
84+25	113+41	LT	2926.55*	4.0	1.5	1297.0	108.9
114+32	119+10	LT	478.0	4.0	1.5	210.0	17.6
119+10	119+42	LT	32.0	7.0	1.5	24.0	2.0
119+42	119+88	LT	46.0	9.0	1.5	45.0	3.8
119+88	121+77	LT	189.0	8.0	1.5	167.0	14.0
121+77	122+04	LT	27.0	6.0	1.5	18.0	1.5
122+04	130+68	LT	864.0	4.0	1.5	373.0	31.3
131+09	134+71	LT	362.0	4.0	1.5	162.0	13.6
135+30	148+70	LT	1340.0	4.0	1.5	597.0	50.1
149+55	162+31	LT	1265.1*	4.0	1.5	562.0	47.2
164+27	165+79	LT	152.0	4.0	1.5	67.0	5.6
184+25	187+40	LT	315.0	4.0	1.5	134.0	11.3
						5440.8	457.0

*SEE STA. EQUATION ON PLANS

6 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (cont.)								
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	AVERAGE WIDTH (FEET)	DEPTH (INCHES)	AREA TO BE PRIMED (SQ. YDS.)	QUANTITY (TONS)	
MAINLINE-SHOULDER- RIGHT								
7+42	22+36	RT	1494.0	4.0	1.5	663.0	55.7	
23+17	41+71	RT	1851.2*	4.0	1.5	826.0	69.4	
42+01	50+10	RT	824.0	4.0	1.5	364.8	30.6	
65+04	67+88	RT	284.0	4.0	1.5	126.0	10.6	
84+25	102+22	RT	1797.0	4.0	1.5	822.0	69.0	
102+22	106+40	RT	428.55*	2.0	1.5	85.0	7.1	
106+40	111+29	RT	489.0	4.0	1.5	214.0	18.0	
111+96	126+25	RT	1406*	3.0	1.5	442.0	37.1	
126+25	126+55	RT	30.0	6.5	1.5	22.0	1.8	
126+55	128+50	RT	195.0	9.0	1.5	195.0	16.4	
128+50	129+12	RT	62.0	7.0	1.5	50.0	4.2	
129+12	129+63	RT	51.0	4.0	1.5	23.0	1.9	
129+63	129+93	RT	30.0	7.0	1.5	24.0	2.0	
129+93	130+13	RT	20.0	10.0	1.5	22.0	1.8	
130+13	130+33	RT	20.0	7.0	1.5	16.0	1.3	
130+33	149+00	RT	1867.0	4.0	1.5	828.0	69.6	
149+02	165+80	RT	1577.1*	4.0	1.5	700.0	58.8	
184+25	186+42	RT	217.0	4.0	1.5	96.0	8.1	
186+42	186+53	RT	11.0	5.0	1.5	6.0	0.5	
186+53	187+11	RT	58.0	5.0	1.5	33.0	2.8	
187+11	187+39	RT	59.0	2.0	1.5	13.0	1.1	
						5570.8	467.9	
Side Roads								
KRUGER ROAD		RT	91.0	15.0	1.5	151.0	12.7	
BIRCH LAKES DRIVE		LT	68.0	9.0	1.5	68.0	5.7	
HOLMES AVENUE		RT	69.0	12.0	1.5	95.0	8.0	
LOCHANORA DRIVE		LT	107.0	17.0	1.5	200.0	16.8	
MILTON ROAD		RT	80.0	14.0	1.5	123.0	10.3	
MILTON ROAD		LT	112.0	16.0	1.5	195.0	16.4	
TOPANGA TRAIL		LT	41.0	13.0	1.5	61.0	5.1	
POND SHORE DRIVE		LT	63.0	17.0	1.5	122.0	10.2	
SCHWERMAN ROAD		LT	84.0	15.0	1.5	136.0	11.4	
SCHWERMAN ROAD		RT	92.0	22.0	1.5	223.0	18.7	
BARNSWALLOW LANE		LT	209.0	15.0	1.5	357.0	30.0	
IL ROUTE 176		LT	108.0	6.0	1.5	74.0	6.2	
IL ROUTE 176		RT	63.0	14.0	1.5	97.0	8.1	
						1902.0	159.8	
PAY ITEM 40603340 112 lbs./Sq. Yd./in.						SUBTOTAL	48811.4	4151.3
						5% CONTINGENCY	2440.6	207.6
						TOTAL	51252.0	4358.8

*SEE STA. EQUATION ON PLANS

NO.	REVISIONS / REMARKS	DATE	BY	SURVEYOR
1	PER LCDOT REVIEW COMMENTS	10/06/09	EB	DSGMR/LIAISON



FAIRFIELD ROAD
RESURFACING 2009



FAIRFIELD RD RESURFACING
SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH 49	113	08-00999-01-RS	6	60