

7 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"							
FROM	TO	LT/RT	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT.)	AREA (SQ. YDS.)	
1+58	5+25	LT	367	32	11744.0	1304.9	
1+58	5+25	RT	367	13.0	4771.0	530.1	
186+53	187+65.63	LT	112.63	22.0	2477.9	275.3	
186+53	187+65.63	RT	112.63	33.0	3716.8	413.0	
PAY ITEM					SUBTOTAL	22709.7	2523.3
44000155					10% CONTINGENCY	2271.0	252.3
					TOTAL	24980.6	2775.6

8 HOT-MIX ASPHALT SURFACE REMOVAL, 2"							
FROM	TO	LT/RT	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT.)	AREA (SQ. YDS.)	
5+75	7+92	LT	217	13	2821.0	313.4	
5+75	7+92	RT	217	1.7	368.9	41.0	
7+92	11+22.68	LT	330.68	17.1	5667.9	629.8	
7+92	11+22.68	RT	330.68	12.1	3991.3	443.5	
11+22.68	22+98	LT	1175.32	11.3	13281.1	1475.7	
11+22.68	39+55	RT	2832.32	11.1	31438.8	3493.2	
28+00	49+60	LT	2160	11.1	23997.6	2666.4	
39+55	42+32.69	RT	277.69	19.4	5373.3	597.0	
42+32.69	49+60	RT	727.31	11.0	8000.4	888.9	
65+50	67+30	LT	180.0	11.0	1980.0	220.0	
65+50	67+30	RT	180.0	11.0	1980.0	220.0	
84+75	165+30.00	LT	8055.0	11.0	88605.0	9845.0	
84+75	102+22.00	RT	1747.0	11.0	19269.4	2141.0	
106+90.36	111+29.00	RT	438.6	11.0	4824.6	536.1	
116+60	149+00	RT	3240	11.0	35640.0	3960.0	
149+00	149+92.28	RT	92.28	13.7	1264.2	140.5	
149+92.28	165+30	RT	1537.72	11.0	16914.9	1879.4	
SEE STA. EQUATION ON PLANS							
PAY ITEM					SUBTOTAL	265418.4	29490.9
44000157					10% CONTINGENCY	26541.8	2949.1
					TOTAL	291960.2	32440.0

9 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH							
FROM	TO	LT/RT	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT.)	AREA (SQ. YDS.)	
5+25	5+75	LT	50	19.0	950.0	105.6	
5+25	5+75	RT	50	19.0	950.0	105.6	
5+75	7+92	LT	217	12.0	2604.0	289.3	
5+75	7+92	RT	217	12.0	2604.0	289.3	
22+98.71	28+50	LT	551.29	14.0	7718.1	857.6	
102+22	106+90.36	RT	468.36	13.0	6088.7	676.5	
111+29	116+60	RT	531	13.0	6903.0	767.0	
119+10.16	122+17	LT	306.84	8.0	2454.7	272.7	
126+25	129+12	RT	287	9.0	2583.0	287.0	
163+59	164+12	LT	53	9.0	477.0	53.0	
186+23	186+53	LT	30	16.0	480.0	53.3	
186+23	186+53	RT	30	22.0	660.0	73.3	
SEE STATION EQUATION ON PLANS							
PAY ITEM					SUBTOTAL	34472.5	3830.3
44000198					10% CONTINGENCY	3447.2	383.0
					TOTAL	37919.7	4213.3

10 PAVED SHOULDER REMOVAL							
FROM	TO	LT/RT	LENGTH (FEET)	AVG. WIDTH (FEET)	AREA (SQ. FT.)	AREA (SQ. YDS.)	
Mainline Shoulder							
7+42.00	22+26.06	LT	1484.06	2.0	2968.1	329.8	
7+42.00	22+26.06	RT	1484.06	2.1	3116.5	346.3	
23+16.81	39+50.76	RT	1633.95	2.1	3349.6	372.2	
28+00	50+10	LT	2188.40	2.2	4814.5	534.9	
42+32.70	50+10	RT	777.30	2.0	1554.6	172.7	
65+00	66+38.00	LT	138.00	2.0	276.0	30.7	
65+00	67+80	RT	280.00	2.0	560.0	62.2	
84+25	113+30.06	LT	2925.55	2.1	6026.6	669.6	
84+25	102+71.91	RT	1846.91	2.1	3878.5	430.9	
106+40.36	111+29.00	RT	488.64	2.0	977.3	108.6	
114+42.37	119+10.17	LT	467.80	2.0	935.6	104.0	
122+17.00	130+66.31	LT	803.31	2.1	1687.0	187.4	
116+10.00	126+25.04	RT	969.04	2.1	1986.5	220.7	
129+11.79	149+00	RT	1988.21	2.3	4493.4	499.3	
131+10.13	134+67.66	LT	356.93	2.0	713.9	79.3	
135+33.89	148+70.52	LT	1336.63	2.0	2673.3	297.0	
149+55.64	162+31.13	LT	1253.69	2.1	2632.7	292.5	
149+91.74	165+80	RT	1566.46	2.2	3446.2	382.9	
164+12.41	165+80	LT	167.59	2.0	335.2	37.2	
184+25	187+02.00	LT	277.20	2.1	582.1	64.7	
184+25	186+53.00	RT	228.20	2.1	479.2	53.2	
Side Roads							
Kruger Road		LT			88.9	9.9	
Kruger Road		RT			98.4	10.9	
Holmes Avenue		RT			90.9	10.1	
Lochenora Drive		LT			102.6	11.4	
PAY ITEM					SUBTOTAL	47867.6	5318.6
44004250					10% CONTINGENCY	4786.8	531.9
					TOTAL	52654.3	5850.5