

39 SEEDING (COMPLETE)							
FROM STATION	TO STATION	LT/RT	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ FT)	AREA (SQ YDS)	
7+42	18+8.28	LT	1066.28	5.0	5331.40	592.38	
7+42	18+6.20	RT	1017.44	5.0	5087.20	565.24	
20+00.44	22+26.06	LT	225.62	5.0	1128.10	125.34	
20+6.75	22+26.06	RT	219.31	5.0	1096.55	121.84	
23+16.81	41+52.39	RT	1816.11	5.0	9080.55	1008.95	
28+00	50+10	LT	1987.12	5.0	9935.60	1103.96	
42+27.15	50+10	RT	782.85	5.0	3914.25	434.92	
65+00	66+38.00	LT	138.00	5.0	690.00	76.67	
65+00	67+80	RT	280.00	5.0	1400.00	155.56	
84+25	113+30.06	LT	2841.07	5.0	14205.35	1578.37	
84+25	102+71.91	RT	1770.60	5.0	8853.00	983.67	
106+40.36	111+29.00	RT	484.57	5.0	2422.85	269.21	
114+42.37	119+21.07	LT	478.70	5.0	2393.50	265.94	
116+10.00	126+37.02	RT	969.17	5.0	4845.85	538.43	
121+90.55	130+66.31	LT	809.32	5.0	4046.60	449.62	
128+97.46	149+00	RT	1876.00	5.0	9380.00	1042.22	
131+10.13	134+67.66	LT	357.53	5.0	1787.65	198.63	
135+33.89	148+70.52	LT	1336.63	5.0	6683.15	742.57	
149+55.64	162+31.13	LT	1225.98	5.0	6129.90	681.10	
149+91.74	165+80	RT	1488.70	5.0	7443.50	827.06	
164+12.41	165+80	LT	167.59	5.0	837.95	93.11	
184+25	187+02.00	LT	277.00	5.0	1385.00	153.89	
184+25	186+53.00	RT	228.00	5.0	1140.00	126.67	
					SUBTOTAL	109218.0	12135.3
PAY ITEM XX006343					10% CONTINGENCY	10921.8	1213.5
					TOTAL	120139.7	13348.9
SEE STA. EQUATION ON PLANS							
40 HOT-MIX ASPHALT - DRIVEWAY REMOVAL & REPLACEMENT							
PAY ITEM XX004238					4 DRIVEWAYS @ 72.6 S.Y. EACH		AREA (SQ. YDS.) 290.4

41 HOT-MIX ASPHALT SURFACE REMOVAL - DRIVEWAY BUTT JOINT							
FROM	TO			LT/RT	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ. YDS.)
DRIVEWAY BUTT JOINTS							
	10+86.71			RT	21.0	4.0	9.3
	31+42.8			LT	11.0	4.0	4.9
	33+05.51			RT	13.0	4.0	5.8
	43+95.37			LT	16.4	4.0	7.3
	47+79.96			LT	16.1	4.0	7.1
	86+45.53			RT	17.3	4.0	7.7
	93+12.81			LT	22.0	4.0	9.8
	99+10.32			RT	17.0	4.0	7.6
	101+40.03			RT	9.0	4.0	4.0
	106+92.18			LT	10.0	4.0	4.5
	122+52.38			RT	12.5	4.0	5.6
	122+94.89			LT	13.0	4.0	5.8
	129+77.02			RT	18.0	4.0	8.0
	131+85.56			RT	14.0	4.0	6.2
	140+23.29			RT	13.0	4.0	5.8
	153+69.72			RT	13.6	4.0	6.1
	155+15.86			LT	11.5	4.0	5.1
	157+09.85			RT	16.5	4.0	7.3
	157+58.01			LT	12.5	4.0	5.6
	160+24.56			RT	11.0	4.0	4.9
	165+09.15			RT	12.5	4.0	5.6
					SUBTOTAL	133.8	
PAY ITEM XX007365					10% CONTINGENCY		13.4
					TOTAL		147.2
42 MAILBOX POST							
PAY ITEM XX206400					EACH		18