

SUMMARY OF QUANTITIES				1000-2A ROADWAY 80% HPP 20% STATE	Y031-1F SIGNALS 80% HPP 20% STATE	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION	1000-2A ROADWAY NON-PART 100% CITY OF EVANSTON (LOCAL FUNDS)
CODE NO	PAY ITEM	UNIT	QUANTITY				
20101000	TEMPORARY FENCE	FOOT	8,440	8,440			
20101100	TREE TRUNK PROTECTION	EACH	211	211			
20101200	TREE ROOT PRUNING	EACH	211	211			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	36	36			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	70	70			
20200100	EARTH EXCAVATION	CU YD	2,342	2,342			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,285	2,285			
20400800	FURNISHED EXCAVATION	CU YD	62	62			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	77	77			
20800150	TRENCH BACKFILL	CU YD	2,964	2,964			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17,272	17,272			
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200	200.0			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	214	214			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	214	214			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	214	214			
25200100	SODDING	SQ YD	17,272	17,272			
25200200	SUPPLEMENTAL WATERING	UNIT	260	260			
28000400	PERIMETER EROSION BARRIER	FOOT	459	459			
28000500	INLET AND PIPE PROTECTION	EACH	1	1			
28000510	INLET FILTERS	EACH	76	76			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	6,951	6,951			
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	465	465			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,970	3,970			
40600300	AGGREGATE (PRIME COAT)	TON	82	82			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,052	1,052			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	282	282			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,751	1,751			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,607	1,607			
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	2,899	2,899			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	638	638			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	198	198			
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	23,075	23,075			
42400800	DETECTABLE WARNINGS	SQ FT	869	869			

• SPECIALTY ITEM

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED - CEC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHERIDAN ROAD /FOREST AVENUE SUMMARY OF QUANTITIES			F.A.U. RTE. 2865	SECTION 08-00250-02-PV	COUNTY COOK	TOTAL SHEETS 79	SHEET NO. 4
	PLOT SCALE = #SCALE#	CHECKED - DWB	REVISED -		NOT TO SCALE	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 63417			
	PLOT DATE = #DATE#	DATE - 04/09/2010	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							