

SUMMARY OF QUANTITIES				1000-2A ROADWAY 80% HPP 20% STATE	Y031-1F SIGNALS 80% HPP 20% STATE	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION	1000-2A ROADWAY NON-PART 100% CITY OF EVANSTON (LOCAL FUNDS)
CODE NO	PAY ITEM	UNIT	QUANTITY				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,277	3,277			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	663	663			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,028	1,028			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	433	433			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	306	306			
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	338	338			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	91		91		
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	162		162		
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	65		65		
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	102		102		
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	59		59		
* 81400100	HANDHOLE	EACH	3		3		
* 81400300	DOUBLE HANDHOLE	EACH	1		1		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	301		301		
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	584		584		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	807		807		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,140		1,140		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	118		118		
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	219		219		
* 87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	1		1		
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4		4		
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2		2		
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28		28		
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4		
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		3		
* 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2		
* 88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1		
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6		6		
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	2		2		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	156		156		
* 88700200	LIGHT DETECTOR	EACH	2			2	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6		6		
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	12	12			

\* SPECIALTY ITEM