

SUMMARY OF QUANTITIES

CODE NO	PAY ITEM	UNIT	QUANTITY	I000-2A ROADWAY 80% HPP 20% STATE	Y031-1F SIGNALS 80% HPP 20% STATE	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION	I000-2A ROADWAY NON-PART 100% CITY OF EVANSTON (LOCAL FUNDS)
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	247	247			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	152	152			
X0323677	STREET SWEEPING	HOURL	30	30			
X0323868	DRAINAGE RESTRICTOR	EACH	7	7			
X0324878	ADJUSTING SANITARY SEWER SERVICE LINE	EACH	5	5			
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	5,460	5,460			
X0325537	ELASTOMERIC CHECK VALVE 30" DIAMETER	EACH	1	1			
X0326415	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 16"	FOOT	844	844			
* X0326740	LINE MANHOLE	FOOT	67				67
X0517100	STORM SEWERS, DUCTILE IRON PIPE 8"	FOOT	26	26			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4			
X4023000	TEMPORARY ACCESS (ROAD)	EACH	7	7			
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1			
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1		
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1		
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	568		568		
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	181			181	
XX002118	STORM SEWER DUCTILE IRON 12"	FOOT	1,852	1,852			
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1.0			
XX004018	REMOVE AND RELAY BRICK SIDEWALK	SQ FT	278	278			
XX004774	BRICK DRIVEWAY REMOVAL AND REPLACEMENT	SQ FT	624	624			
* XX004812	VIDEO TAPING OF SEWERS	FOOT	18,248				18,248
* XX005721	WATER METER TO BE ADJUSTED	EACH	1				1
* XX006891	CIPP LINER FOR SANITARY SEWER MAIN 8"	FOOT	28				28
* XX007078	VALVE VAULTS TO BE LINED	EACH	6				6
XX007079	CONCRETE RIBBON	FOOT	1,445	1,445			
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	3,206	3,206			
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	51	51			
Z0004910	HOT-MIX ASPHALT FOR PATCHING POTHOLES (HOT MIX)	TON	25	25			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0019600	DUST CONTROL WATERING	UNIT	100	100			
Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	14	14			
Δ Z0076600	TRAINEES	HOURL	1,000	1,000			
LR442020	BITUMINOUS PATCHING MIXTURE (GROUP II)	TON	15	15			
X4200408	PORTLAND CEMENT CONCRETE PAVEMENT 8" SPECIAL	SQ YD	1,093				1,093

* SPECIALTY ITEM

Δ Y080

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - CEC DRAWN - CEC CHECKED - DWB DATE - 04/09/2010	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHERIDAN ROAD /FOREST AVENUE SUMMARY OF QUANTITIES	F.A.U. RTE. 2865	SECTION 08-00250-02-PV	COUNTY COOK	TOTAL SHEETS 79	SHEET NO. 8
						SHEET NO. 5 OF 5 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 63417		