

SUMMARY OF QUANTITIES

SPECIALTY ITEM	ITEM	DESCRIPTION	UNIT	Y-052 TOTAL QUANTITY
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	110
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30
	20101000	TEMPORARY FENCE	FOOT	60
	20200100	EARTH EXCAVATION	CU YD	830
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	65
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	65
	20800250	TRENCH BACKFILL, SPECIAL	CU YD	10
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1800
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40
*	25000830	HYDRAULIC SEEDING	ACRE	0.40
*	25100115	MULCH, METHOD 2	ACRE	0.40
*	25200110	SODDING, SALT TOLERANT	SQ YD	300
	28000400	PERIMETER EROSION BARRIER	FOOT	4000
	28000510	INLET FILTERS	EACH	2
	35102100	AGGREGATE BASE COURSE, TYPE B 9"	SQ YD	1500
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	260
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	300
	42400800	DETECTABLE WARNINGS	SQ FT	130
	44000100	PAVEMENT REMOVAL	SQ YD	70
	44000600	SIDEWALK REMOVAL	SQ FT	300
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	30
	67100100	MOBILIZATION	L SUM	1
*	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	72000100	SIGN PANEL - TYPE 1	SQ FT	400
	72900100	METAL POST TYPE A	FOOT	1920
*	A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	14
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	12
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
	XX002258	STRUCTURES TO BE ADJUSTED	EACH	1
	XX006459	LOCKABLE REMOVABLE POST	EACH	6
*	XX006910	TREE PROTECTION, SPECIAL	EACH	17

*INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME = MAGOLDEN	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	VILLAGE OF DOWNERS GROVE SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\DownersGrove\088569\Civil\088569_004.dwg		DRAWN -	REVISED -			09-00099-00-BT	DUPAGE	30	3	
PLOT SCALE = NTS		CHECKED -	REVISED -			CONTRACT NO. 63451				
PLOT DATE = 3/19/2010		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT		