

**SUMMARY OF QUANTITIES**

CODE	PAY ITEM DESCRIPTION	UNIT	1000	1000
			TOTAL QUANTITY	80% FEDERAL 20% LOCAL
20200100	EARTH EXCAVATION	CU YD	3,600	3,600
~ 20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	650	650
20800150	TRENCH BACKFILL	CU YD	75	75
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	300	300
25200100	SODDING	SQ YD	300	300
25200200	SUPPLEMENTAL WATERING	UNIT	50	50
~ 28000510	INLET FILTERS	EACH	20	20
~ 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,850	1,850
40600300	AGGREGATE (PRIME COAT)	TON	40	40
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	250	250
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	525	525
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	8,000	8,000
42101300	PROTECTIVE COAT	SQ YD	250	250
~ 42300720	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH, SPECIAL	SQ YD	50	50
~ 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	1,000	1,000
~ 42400800	DETECTABLE WARNINGS	SQ FT	64	64
~ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4,700	4,700
~ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	500	500
~ 44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	8,000	8,000
~ 44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	1,000	1,000
550A0330	STORM SEWERS, CLASS A, TYPE 2 10"	FOOT	183	183
~ 60213300	CATCH BASINS, SPECIAL	EACH	11	11
~ 60224600	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
~ 60238900	INLETS, TYPE A, SPECIAL, TYPE 1 FRAME, OPEN LID	EACH	2	2
~ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10
~ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
~ 60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	500	500
67100100	MOBILIZATION	L SUM	1	1

\* DENOTES SPECIALTY ITEM  
 ~ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\60009001 - Broadway Ave Reconstruction\DETAILS.dwg Apr 19, 2010 - 11:23am

**HANCOCK ENGINEERING**  
 Civil Engineers  
 Municipal Consultants  
 Established 1911

1911 Broadway Road  
 Wheeling, Illinois 60090-2700  
 Phone: 708-964-6300  
 Fax: 708-964-6212

USER NAME -	DESIGNED - WOP	REVISED -
PLOT SCALE -	DRAWN - MK/LEV/DMM	REVISED -
PLOT DATE -	CHECKED - WOP	REVISED -
	DATE - 3-29-10	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>		
SCALE: NOT TO SCALE	SHEET NO. 1 OF 2 SHEETS	STA. TO STA.

ROUTE NO. 2406	SECTION 09-00114-00-FP	COUNTY COOK	TOTAL SHEETS 33	SHEET NO. 4
FIELD BOOK NO. 1588/AERIALS/LL		CONTRACT NO. 63455		
FED. ROAD DIST. NO. 1 ILLINOIS   FED. AID PROJECT ARA-M-9003 (516)				