

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, VILLAGE OF LOMBARD STANDARDS, SUMMARY OF QUANTITIES
3	GENERAL NOTES
4-5	SCHEDULE OF QUANTITIES
6-7	TYPICAL SECTIONS
8-12	PLAN SHEETS
13-17	PAVEMENT MARKING SHEETS
18-19	VILLAGE OF LOMBARD STANDARD DETAILS
20	TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
21	TC-22 TEMPORARY INFORMATION SIGNING
22	BD-8 DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
23	BD-32 BUTT JOINT AND HMA TAPER DETAILS
24	TC-13 DISTRICT 1 TYPICAL PAVEMENT MARKINGS
25	TC-16 PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING

HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
424001-05	CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C AND D PATCHES
602011-01	CATCH BASIN, TYPE C
602301-02	INLET - TYPE A
602401-02	MANHOLE, TYPE A
602701-02	MANHOLE STEPS
604001-03	FRAMES AND LIDS, TYPE 1
604006-04	FRAME AND GRATE, TYPE 3
604041-02	FRAME AND GRATE, TYPE 9
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701501-05	URBAN LANE CLOSURE, 2L, 2W UNDIVIDED
701606-06	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES

VILLAGE OF LOMBARD STANDARD DRAWINGS

DRAWING NO.	TITLE
PAVEMENT 2	SIDEWALK CROSS SECTION
PAVEMENT 4	SIDEWALK CONSTRUCTION
PAVEMENT 5	TYPICAL PAVEMENT CROSS-SECTION
PAVEMENT 6	RESIDENTIAL DRIVEWAY APRON
PAVEMENT 7	COMMERCIAL DRIVEWAY APRON
PAVEMENT 8	CURB AND GUTTER
PAVEMENT 9	STORM SEWER INLET CURB AND GUTTER
STORM 2	INLET TYPE A
STORM 4	CATCH BASIN TYPE C
STORM 7	RIM ADJUSTMENTS PAVED AREA
STORM 8	RIM ADJUSTMENTS IN CURB LINE
STORM 12	GRATE BOX INLET
SANITARY 1	SANITARY MANHOLE

SUMMARY OF QUANTITIES

PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	PARTICIPATING QUANTITY 1000	NON PARTICIPATING QUANTITY
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	16	16	
25200200	SUPPLEMENTAL WATERING	UNIT	52	52	
25200700	SODDING, SPECIAL	SQ YD	1,730	1,730	
28000510	INLET FILTERS	EACH	64	64	
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	16	16	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	51	51	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,437	2,437	
40600300	AGGREGATE (PRIME COAT)	TON	37	37	
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	20	20	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75 N50	TON	1,280	1,280	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	280	280	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,070	3,070	
42001300	PROTECTIVE COAT	SQ YD	1,597	1,597	
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	11,815	4,577	7,238
42400800	DETECTABLE WARNINGS	SQ FT	416	416	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	24,365	24,365	
44000600	SIDEWALK REMOVAL	SQ FT	12,497	5,259	7,238
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,239	3,239	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	33	33	
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	17	17	
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	2,459	2,459	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2	
60250300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	1	1	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4	
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5	
60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	1	1	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	4	4	
60262700	INLETS TO BE RECONSTRUCTED	EACH	4	4	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3	
60265800	VALVE VAULTS TO BE ADJUSTED (SPECIAL)	EACH	2	2	
60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	1	1	
60266700	VALVE BOXES TO BE RECONSTRUCTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	41	41	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	61	61	
60404300	FRAMES AND GRATES, TYPE 3	EACH	6	6	
60404600	FRAMES AND GRATES, TYPE 9	EACH	1	1	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	40	40	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	73		73
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	5,048		5048
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	158		158
78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	115		115
78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	542		542
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	180		180
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	26	26	
X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	1,730	1,730	
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT	SQ YD	688	688	
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1	
XX003829	DRIVEWAY APPROACH REMOVAL AND REPLACEMENT	SQ YD	275	275	
XX007509	REMOVE AND REPLACE SANITARY MANHOLES, 4' DIAMETER, 0-8 FEET DEEP	EACH	5	5	
XX007510	REMOVE AND REPLACE SANITARY MANHOLES, 4' DIAMETER, 8-12 FEET DEEP	EACH	4	4	
XX008264	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL)	FOOT	32	32	
Z0076600	TRAINEES	hour	500	500.00	

* DENOTE SPECIALTY ITEM
 ** INDICATES NON-STANDARD ITEM COVERED BY SPECIAL PROVISIONS
 Δ YOS

I:\CRYSTAL LAKE\LOMBARD\090318-MAIN ST LAPF\CADD-SURVEY\DRAWINGS\DWGS\090318-GEN NOTES.DWG 02
 Plotted: 4/19/2010 9:53 AM By: 560KAR
 Copyright © 2010, By Baxter & Woodman, Inc.
 State of Illinois - Professional Design Firm
 License No. - 184-001121 - Expires 4-30-11



DESIGNED - TMS	REVISED -
DRAWN - KAR	REVISED -
CHECKED -	REVISED -
DATE - 03-08-10	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, HIGHWAY STANDARDS,
 VILLAGE OF LOMBARD STANDARDS, SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2611	01-00142-00-RS	DuPAGE	25	2
C-91-427-10		CONTRACT NO. 63456		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

SCALE: PROJECT NO: 090318 STA. TO STA.