

CURVE DATA  
 Dc= 16°-01'-36"  
 Δ=44°-51'-17"  
 R=357.50'  
 L=279.87'  
 E=29.25'  
 SE=4%

END OF PROJECT  
 STA 25+18


MATCHLINE 19+50

**DEMOLITION PLAN NOTES:**

1. REMOVE SIGN PANEL ASSEMBLY - TYPE A OR TYPE B, REMOVE SIGN PANEL- TYPE 1 - ALL EXISTING SIGN PANELS TO BE REMOVED AND CLEANED. SEE DETAIL 4, SHEET 21, THE SIGN SCHEDULE AND PLANS.
2. REMOVE SIGN PANEL - TYPE 1 - SIGNS ATTACHED TO LIGHTPOLES AND TRAFFIC POSTS TO BE REMOVED AND CLEANED. SEE DETAIL 4, SHEET 21, THE SIGN SCHEDULE AND PLANS.
2. BUS SHELTER REMOVE AND RELOCATE
3. TREE REMOVAL (6 TO 15 UNITS)
4. CONCRETE REMOVAL
5. REMOVE TEMPORARY WOOD POLE
6. REMOVE TIMBER RETAINING WALL (AVG. EXPOSED HEIGHT 2.25')
7. EARTH EXCAVATION
8. SOD STRIPPING, 2" DEPTH
9. RETAINING WALL REMOVAL
10. SELECTIVE CLEARING
11. SIGN REMOVAL, SPECIAL
12. TREE TRANSPLANT
13. PERIMETER EROSION BARRIER

**LEGEND**

- EXISTING SHADE TREE
- EXISTING EVERGREEN TREE
- EXISTING SHRUB
- EXISTING HEDGE/TREE LINE
- EXISTING OVERHEAD ELEC LINES
- EXISTING SIGN
- SELECTIVE CLEARING
- EXISTING GAS LINE
- EXISTING SANITARY SEWER
- EXISTING STORM SEWER
- EXISTING WATER MAIN
- EXISTING OVERHEAD METRA LINE
- EXISTING UNDERGROUND COMCAST LINE
- EXISTING UNDERGROUND ELEC LINE
- EXISTING RAILROAD LINE
- CONCRETE REMOVAL
- PERIMETER EROSION BARRIER



FILE NAME = ex. cond demo plan - 8				USER NAME =				DESIGNED = BCL/RJA				REVISED =				STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				EXISTING SIGN INVENTORY / DEMOLITION PLAN				F.A.U. RTE. 2843		SECTION 08-00124-00-LS		COUNTY COOK		TOTAL SHEETS 24		SHEET NO. 8	
PLOT SCALE =				DRAWN = RJA				CHECKED = BCL				REVISED =												SCALE: SHEET NO. 8 OF 24 SHEETS STA. 19+50 TO STA. 25+18				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					
PLOT DATE = 1.22.10				CHECKED = BCL				REVISED =												CONTRACT NO. 63463													