



DETECTOR LOOP REPLACEMENT AT OGDEN AVENUE (NORTH)

THERMOPLASTIC STRIPING CODE

- (A) PROPOSED DOUBLE SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - CENTER LINE 4", 11" O/C
- (B) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 4"
- (C) PROPOSED SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - LINE 4"
- (D) PROPOSED SKIP-DASH YELLOW THERMOPLASTIC PAVEMENT MARKING - LINE 4" - 10' DASH, 30' SKIP (LANE LINE)
- (E) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 6" (LANE LINE)
- (F) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 6" (CROSSWALK LINE)
- (G) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 6" - 2' DASH, 6' SKIP (LANE LINE)
- (H) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 12"
- (I) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LINE 24" (STOP BAR)
- (J) PROPOSED SOLID WHITE THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS
- (K) PAINT PAVEMENT MARKING

DETECTOR LOOPS

- (L) PROPOSED DETECTOR LOOP REPLACEMENT

NOTE: ALL "ARROW" and "ONLY" MARKINGS SHALL BE 8" IN HEIGHT.

NOTE: PROPOSED DOUBLE SOLID YELLOW THERMOPLASTIC PAVEMENT MARKING - CENTER LINE 4", 11" O/C (NOTE: (A)) IS MEASURED PER LINE. TOTAL QUANTITY AND PAYMENT LENGTH IS FOR EACH LINEAR FOOT OF SINGLE 4" STRIPE INSTALLED.

NOTE: SHORT-TERM PAVEMENT MARKING IS PROPOSED ON THE MILLED PAVEMENT, NEW BINDER AND ON THE NEW SURFACE. SEE ARTICLE 703.04 OF THE LATEST EDITION OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".

NOTE: PROPOSED STRIPING IS BEING REPLACED IN THE SAME LOCATION AS EXISTING STRIPING.

FOR TYPICAL CROSS SECTION OF NEW PAVEMENT WORK SEE SHEET X

IMPORTANT!
FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES INDICATED IN TITLE BLOCK.

Frank Novotny & Associates, Inc.
225 Midway Drive • Willmetts, IL • 60127 • Telephone: (630) 837-8660 • Fax: (630) 837-0132
ILLINOIS PROFESSIONAL DESIGN FIRM NO. 194-00028

FILE NAME =	USER NAME =	DESIGNED - AMS	REVISED - AMS 3/09/10
		DRAWN - TRB	REVISED -
	PLOT SCALE = 1" = 40'	CHECKED - TPG	REVISED -
	PLOT DATE =	DATE - 1/28/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN: AUSTIN BOULEVARD -
STA. 45+40 TO STA. 61+25 (STRIPING)

SCALE: 1" = 40' SHEET NO. OF SHEETS STA. 45+40 TO STA. 61+25

F.A. - R.T.E. - 2790	SECTION - 10-00212-00-RS	COUNTY - COOK	TOTAL SHEETS - 16	SHEET NO. - 7
CONTRACT NO. 63464			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ARA-9003(645)	