

SCHEDULES OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	
8	LT STA 30+49.2 @	29.0'
6	LT STA 30+56.5 @	46.4'
8	LT STA 30+62.3 @	34.9'
6	LT STA 30+72.3 @	52.4'
8	LT STA 30+74.5 @	35.2'
15	LT STA 30+87.9 @	43.4'
6	LT STA 30+89.3 @	45.9'
8	LT STA 31+01.5 @	36.7'
14	LT STA 31+03.8 @	26.9'
8	LT STA 31+05.5 @	64.7'
14	LT STA 31+07.8 @	22.5'
8	LT STA 31+21.1 @	29.6'
10	LT STA 31+22.3 @	33.7'
8	LT STA 31+22.4 @	68.7'
14	LT STA 31+22.4 @	56.1'
12	LT STA 31+45.7 @	70.3'
6	LT STA 31+48.9 @	33.8'
6	LT STA 31+50.1 @	70.1'
10	LT STA 31+54.5 @	49.8'
14	LT STA 31+55.2 @	68.0'
8	LT STA 31+61.3 @	64.2'
6	LT STA 31+75.7 @	55.6'
8	LT STA 31+83.3 @	48.3'
14	LT STA 32+02.7 @	57.7'
12	LT STA 32+36.0 @	68.8'
14	LT STA 32+45.0 @	61.1'
8	LT STA 32+54.1 @	54.4'
10	LT STA 32+73.7 @	84.6'
6	LT STA 32+73.7 @	38.8'
6	LT STA 32+74.6 @	39.0'
6	LT STA 32+83.3 @	24.1'
8	LT STA 32+84.2 @	36.3'
6	LT STA 32+87.4 @	29.9'
8	LT STA 32+88.2 @	29.3'
8	LT STA 32+91.4 @	74.1'
14	LT STA 33+02.8 @	24.5'
12	LT STA 33+04.3 @	30.7'
14	LT STA 33+23.9 @	47.2'
14	LT STA 33+30.0 @	24.5'
14	LT STA 44+02.6 @	28.4'
385	TOTAL	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	
24	LT STA 30+44.9 @	55.0'
18	LT STA 30+70.0 @	28.0'
18	LT STA 30+86.4 @	41.7'
20	LT STA 31+17.6 @	25.1'
18	LT STA 31+18.2 @	23.3'
18	LT STA 31+57.5 @	75.4'
18	LT STA 31+67.1 @	70.0'
16	LT STA 31+89.9 @	50.4'
24	LT STA 31+94.6 @	26.3'
20	LT STA 32+45.9 @	38.0'
24	LT STA 32+62.8 @	90.2'
20	LT STA 32+70.1 @	38.8'
16	LT STA 32+98.3 @	64.7'
24	LT STA 33+10.0 @	28.1'
17	LT STA 44+19.0 @	40.0'
295	TOTAL	

20101000 TEMPORARY FENCE

FOOT	LOCATION	
673.0	LT STA 29+57.7 -	33+53.0
169.9	LT STA 44+53.0 -	44+87.1
843	TOTAL	

20101100 TREE TRUNK PROTECTION

EACH	LOCATION	
1	LT STA 29+93.9 @	73.7'
1	LT STA 30+11.0 @	68.0'
1	LT STA 30+13.0 @	66.2'
1	LT STA 30+14.1 @	67.6'
1	LT STA 30+30.1 @	34.0'
1	LT STA 30+31.7 @	46.2'
1	LT STA 30+34.0 @	31.1'
1	LT STA 30+37.7 @	51.0'
1	LT STA 33+19.7 @	82.1'
1	LT STA 33+23.0 @	106.9'
1	LT STA 33+23.8 @	62.2'
1	LT STA 33+23.9 @	47.2'
1	LT STA 33+24.1 @	53.2'
1	LT STA 33+24.5 @	87.1'
1	LT STA 33+29.1 @	67.9'
1	LT STA 33+34.0 @	47.6'
1	LT STA 44+00.9 @	39.3'
1	LT STA 44+13.1 @	81.2'
1	LT STA 44+20.4 @	81.7'
19	TOTAL	

20200100 EARTH EXCAVATION

20400800 FURNISHED EXCAVATION

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED 25% SHRINKAGE	EMBANKMENT	FURNISHED EXCAVATION
29+60.5 TO 33+50.0	685.0	513.8	1,936.9	(1,423.1)
43+90.0 TO 44+50.0	18.7	14.0	2.4	11.6
TOTAL	704	528	1,940	(1,412)

20800150 TRENCH BACKFILL

CU YD	LOCATION	
80.8	LT STA 31+41.8 -	32+61.3
81	TOTAL	

21101625 TOPSOIL FURNISH AND PLACE, 6"

SQ YD	LOCATION	
1,575.4	LT STA 30+40 -	33+25
222.7	LT STA 43+90 -	44+50
1,799	TOTAL	

25002014 SEEDING, CLASS 4A (MODIFIED)

ACRE	LOCATION	REMARKS
0.4	LT STA 30+40 -	33+25 Read Special Provision
0.1	LT STA 43+90 -	44+50 Read Special Provision
0.5	TOTAL	

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION	
1,575.4	LT STA 30+40 -	33+25
222.7	LT STA 43+90 -	44+50
1,799	TOTAL	

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	
190.0	LT STA 30+40 -	33+25
18.4	LT STA 43+90 -	44+50
149	TOTAL	

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	
78.0	LT STA 29+60.6 -	30+38.6
60.3	LT STA 30+38.6 -	30+38.6
327.4	LT STA 30+38.6 -	33+17.2
106.0	LT STA 33+17.3 -	33+51.2
68.3	LT STA 43+88.5 -	44+18.5
66.8	LT STA 44+30.5 -	44+51.4
707	TOTAL	

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	
1	LT STA 31+38.32 @	14.0'
1	LT STA 32+64.81 @	14.0'
1	LT STA 44+27.23 @	14.0'
3	TOTAL	

28100207 STONE RIPRAP, CLASS A4

TON	LOCATION	
1,553.6	LT STA 29+60.5 -	33+00.0
18.1	LT STA 44+18.5 -	44+30.5
1,572	TOTAL	

28200200 FILTER FABRIC

SQ YD	LOCATION	
683.0	LT STA 29+60.5 -	33+00.0
26.3	LT STA 44+18.5 -	44+30.5
710	TOTAL	

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION	
144.5	LT STA 31+29.3 -	32+73.8
18	LT STA 44+18.2 -	44+36.2
163	TOTAL	

50104400 CONCRETE HEADWALL REMOVAL

EACH	LOCATION	
1	LT STA 44+36.9 @	27.9'
1	TOTAL	